

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		X031-2A	
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	775	775	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	5592	5592	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	775	775	
50102400	CONCRETE REMOVAL	CU YD	45	45	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	122.9	122.9	
50300260	BRIDGE DECK GROOVING	SQ YD	131	131	
50300300	PROTECTIVE COAT	SQ YD	146	146	
50606401	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1	
50606402	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2	L SUM	1	1	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	16040	16040	
50800515	BAR SPLICERS	EACH	52	52	
60260100	INLETS TO BE ADJUSTED	EACH	7	7	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7	
67100100	MOBILIZATION	L SUM	1	1	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1	
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1145	1145	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	24793	24793	
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	1850	1850	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8264	8264	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	950	950	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	900	900	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	8667	8667	
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	124	124	
* 78100300	REPLACEMENT REFLECTOR	EACH	248	248	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2889	2889	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	248	248	
20030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
20030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
50600600	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	1	
50600700	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM	1	1	

GENERAL NOTES:

1. THE STANDARDS AND REVISION NUMBERS LISTED SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AMERENIP (GAS & ELECTRIC)
 - AT&T CORPORATION (COMMUNICATIONS)
 - CHARTER COMMUNICATIONS, INC. (CABLE TV)
 - ILLINOIS AMERICAN WATER COMPANY (WATER)
 - AT&T ILLINOIS (COMMUNICATIONS)
 MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY*. NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
4. THE CONTRACTOR SHALL FURNISH AND INSTALL WOOD SIGN SUPPORTS IN ACCORDANCE WITH SECTION 730 OF THE STANDARD SPECIFICATIONS; HOWEVER, INSTALLATION BY METHOD 'A' (ARTICLE 730.04(d)) SHALL BE THE ONLY METHOD PERMITTED.
5. FOR STAGE I, THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER SHALL BE PAINTED YELLOW, FOR STAGE II, THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER SHALL BE PAINTED WHITE. THE COST SHALL BE PAID FOR AS "TEMPORARY PAINT PAVEMENT MARKING - LINE 6" ".
6. PAVEMENT MARKING REMOVAL SHALL BE BY WATER BLAST METHOD.
7. TWO LANE TRAFFIC IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES.
8. 'ROAD CONSTRUCTION AHEAD' AND 'WORK ZONE SPEED LIMIT' SIGNS SHALL BE INSTALLED AS DIRECTED BY THE RESIDENT ENGINEER ON THE SOUTHBOUND RAMP AT IL 162.

COMMITMENTS

NONE

*SPECIALTY ITEMS

Rev. 2-14-08

FILE NAME =	USER NAME = harbaughrd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES, GENERAL NOTES & COMMITMENTS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
α:\projects\ed86306\p1en\p1n26308a.dgn	PLOT SCALE = 50.0000 / IN.	DRAWN -	REVISED -			255	60-88-11	MADISON	42	2
PLOT DATE = 12/19/2007	DATE -	CHECKED -	REVISED -			CONTRACT NO. 76A25				

STAGE CONSTRUCTION SCHEDULE

LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE)	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE)
	FOOT	FOOT	EACH	EACH
NB STAGE I	475		1	
NB STAGE II		475		1
SB STAGE I	475		1	
SB STAGE II		425		1
TOTALS	950	900	2	2

SHOULDER SCHEDULE

LOCATION	LT OR RT	HMA SURFACE REMOVAL, 1"	HMA BINDER USE, 1" (19.0, N90)	INLETS TO BE ADJUSTED
		SQ YD	TONS	EACH
NORTHBOUND				
STA 1471+50 TO STA 1477+55	RT	672.2	94.1	1
STA 1481+59 TO STA 1488+50	RT	767.8	107.5	1
STA 1471+50 TO STA 1477+20	LT	633.3	88.7	1
STA 1481+25 TO STA 1488+50	LT	805.6	112.8	
SOUTHBOUND				
STA 1473+50 TO STA 1476+50	RT	333.3	46.7	1
STA 1480+54 TO STA 1489+75	RT	1023.2	143.2	1
STA 1473+50 TO STA 1476+84	LT	371.1	52.0	1
STA 1480+88 TO STA 1489+75	LT	985.5	138.0	1
TOTALS		5592.0	783.0	7

TEMPORARY PAVEMENT MARKING SCHEDULE

LOCATION	TEMPORARY PAVEMENT MARKING - LINE 4"		TEMPORARY PAINT PAVEMENT MARKING - LINE 6"		SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER
	WHITE	YELLOW	WHITE	YELLOW			
	FT	FT	FT	FT			
NB STAGE I	3202	3124		475		2108.6	32
SB STAGE I	2952	3259	475			2070.2	31
NB STAGE II	4738	1602		475	90.9	2113.2	32
SB STAGE II	4466	1450	425		90.9	1972.0	29
NB					509.9		
SB					453.3		
SUB-TOTAL	15358	9435	900	950			
TOTALS	24,793		1850		1145	8264	124

PERMANENT PAVEMENT MARKING SCHEDULE

LOCATION	PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	REPLACEMENT REFLECTOR (CRYSTAL)
		SQ FT	FT	EACH
NORTHBOUND				
STA 1454+95 TO STA 1464+95	166.7	500	50	50
STA 1471+95 TO STA 1487+95	1333.4	4000	80	80
SOUTHBOUND				
STA 1473+83 TO STA 1488+33	1208.3	3625	73	73
STA 1488+33 TO STA 1489+33	41.7	125	3	3
STA 1495+33 TO STA 1496+33	8.3	25	3	3
STA 1496+33 TO STA 1502+00	94.5	283.6	28	28
STA 1502+00 TO STA 1506+33	36.1	108.4	11	11
TOTALS	2889	8667	248	248

FILE NAME =	USER NAME = harbaughrd	DESIGNED -	REVISED -
c:\projects\ed06306\plan\pin06306a.dgn		DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/20/2007	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: NA SHEET NO. 4 OF 42 SHEETS STA. TO STA.

Rev. 2-14-08

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
255	60-8B-II	MADISON	42	4
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76A25	