

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I=000	-----	-----	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I=000	-----	-----
20200500	EARTH EXCAVATION (WIDENING)	CU YD	1348	1348			54248515	CONCRETE COLLAR	EACH	2	2		
25000210	SEEDING, CLASS 2A	ACRE	0.9	0.9			542A2755	PIPE CULVERTS, CLASS A, TYPE 4 30"	FOOT	23	23		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	81	81			60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	6	6		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	81	81			60107700	PIPE UNDERDRAINS 6"	FOOT	3200	3200		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	81	81			*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	423	423		
25100115	MULCH, METHOD 2	ACRE	0.9	0.9			*63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	8	8		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	90	90			*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		
28000300	TEMPORARY DITCH CHECKS	EACH	4	4			63200310	GUARDRAIL REMOVAL	FOOT	875	875		
28000400	PERIMETER EROSION BARRIER	FOOT	1053	1053			67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10		
28000500	INLET AND PIPE PROTECTION	EACH	4	4			67100100	MOBILIZATION	L SUM	1	1		
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	3378	3378			70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
30201500	LIME	TON	33	33			70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	160	160			70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
35501327	HOT-MIX ASPHALT BASE COURSE, 10 3/4"	SQ YD	1786	1786			70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	192	192			70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	33.3	33.3			70300100	SHORT-TERM PAVEMENT MARKING	FOOT	21819	21819		
40600300	AGGREGATE (PRIME COAT)	TON	161	161			70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	62.4	62.4		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	3407	3407			70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	79898	79898		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	850	850			70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	337	337		
40600990	TEMPORARY RAMP	SQ YD	307	307			70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8878	8878		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	6813	6813			*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	62.4	62.4		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.17	0.17			*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	81,802	81802		
40800030	AGGREGATE (PRIME COAT)	TON	0.8	0.8			*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	337	337		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	45	45			*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	729	729		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	104093	104093			*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	402	402		
44004250	PAVED SHOULDER REMOVAL	SQ YD	1493.3	1493.3			*78200410	GUARDRAIL MARKERS, TYPE A	EACH	20	20		
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	1050	1050			*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3200	3200			78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	375	375		
48100100	AGGREGATE SHOULDERS, TYPE A	TON	400	400			Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1180	1180									
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1423	1423									
48203100	HOT-MIX ASPHALT SHOULDERS	TON	3146	3146									
50105220	PIPE CULVERT REMOVAL	FOOT	16	16									
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2									

Rev. 2-21-08

*SPECIALTY ITEMS

FILE NAME =	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - ---	REVISED - ---		805	(101,102,61-1-1)RS	MARION	81	3			
PLOT SCALE = #SCALE#		CHECKED - ---	REVISED - ---		SCALE: _____ SHEET NO. ____ OF _____ SHEETS STA. _____ TO STA. _____			CONTRACT NO. 76B33				
PLOT DATE = #DATE#		DATE - ---	REVISED - ---		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT							