

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		1000 100% STATE	-----	-----	CODE NO	ITEM		UNIT	-----
X3540050	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10 1/2"	SQ YD	1295	1295							
X4420135	CLASS C PATCHES, TYPE III, 10 1/2 INCH	SQ YD	18	18							
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.8	3.8							
40600300	AGGREGATE (PRIME COAT)	TON	3.7	3.7							
40600990	TEMPORARY RAMP	SQ YD	83	83							
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", NSO	TON	274	274							
44000100	PAVEMENT REMOVAL	SQ YD	1295	1295							
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	2442	2442							
44201360	CLASS C PATCHES, TYPE IV, 10 1/2 INCH	SQ YD	51	51							
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	18	18							
67100100	MOBILIZATION	L SUM	1	1							
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1							
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1085	1085							
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2528	2528							
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	24	24							
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	52	52							
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	121	121							
X78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2528	2528							
X78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	24	24							
X78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	52	52							
78300100	PAVEMENT MARKING REMOVAL	SQ FT	213	213							
80300100	LOCATING UNDERGROUND CABLE	FOOT	60	60							

*\*SPECIALTY ITEMS*