

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 821 FAP 778 FAP 528	•	JEFFERSON SALINE, WHITE	14	3
FUEL ROAD DIST. NO. 7		ILLINOIS	PROJ. NO. PROJECT	

*(1051-1, 121-1, 1241-1)
CONTRACT NO. 78035

100% STATE			RURAL			
CONSTRUCTION TYPE CODE: SAFETY - 2A			QUANTITY			
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	JEFFERSON 041-0021	WHITE 097-0021	SALINE 083-0031
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	12.1	6.4		5.7
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	16.1	7		9.1
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ. FT	500.3	500.3		
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ. FT.	295			295
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	22600		22600	
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	104.9	62.6		42.3
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	317	167		150
X0323078	REMOVE AND RE-ERECT EXISTING BRIDGE RAIL	FOOT	148	98		50
67100100	MOBILIZATION	L SUM	1	0.34	0.33	0.33
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	1		1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.34	0.33	0.33
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1		1
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	97	81		16
70400100	TEMPORARY CONCRETE BARRIER	FOOT	420	220		200
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	190	190		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	882	703		179
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	799.3	500.3		299
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	1	2	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	1	2	1
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	4			4
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		

* SPECIALTY ITEMS