

SUMMARY OF QUANTITIES

F. A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
261103-00148-00-PV	DUPAGE	58	6	6
SUMMARY OF QUANTITIES				
FED. ROAD DISTRICT NO. 7 ILLINOIS FED. AID PROJECT M-8003(521)				
CONTRACT NO. 83952				

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	Y030-1E	Y031-1F	Y060
				ROADWAY	LIGHTING	TRAFFIC SIGNAL	100% VILLAGE
60624600	CORRUGATED MEDIAN	SQFT	45	45			
* 66900200	NON SPECIAL WASTE DISPOSAL	CUYD	210	210			
* 66900450	SPECIAL WASTE PLANS AND REPORT	L. SUM	1	1			
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7			
67100100	MOBILIZATION	L. SUM	1	1			
70101700	TRAFFIC CONTROL AND PROTECTION	L. SUM	1	1			
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1				1
* 72000100	SIGN PANEL - TYPE 1	SQFT	67	14		52.5	
* 72000200	SIGN PANEL - TYPE 2	SQFT	14	14			
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	10	10			
* 72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	4	4			
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	279	279			
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	40	40			
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	20	20			
* 78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQFT	354	354			
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	4184	4184			
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	2409	2409			
* 78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	142	142			
* 78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	306	306			
78300100	PAVEMENT MARKING REMOVAL	SQFT	333	333			
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	139			139	
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	62			62	
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	27			27	
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	17			17	
* 81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	20			20	
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	102			102	
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	363			363	
* 81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	124			124	
* 81400100	HANDHOLE	EACH	4			4	
* 81400300	DOUBLE HANDHOLE	EACH	4			4	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	265		10	255	
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1		1		
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1			1	

* INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

MAIN STREET

DATE: 11/26/07
DESIGNED BY: SJC
CHECKED BY: JRV