



- BENCHMARKS**
- BM VILLAGE OF LOMBARD # 3-020
FOUND 3/4" IRON PIPE WITH PLASTIC CAP AT THE SOUTHEAST CORNER OF THE INTERSECTION OF MAIN STREET AND ROOSEVELT ROAD. VILLAGE OF LOMBARD PUBLISHED ELEVATION 737.79
 - TBM #1 RAILROAD SPIKE (SET) IN POWER POLE IN THE NORTHWEST QUADRANT OF THE INTERSECTION OF MAIN STREET AND EDWARD STREET. ELEVATION 743.00
 - TBM #2 RAILROAD SPIKE (SET) IN POWER POLE ON THE WEST SIDE OF MAIN STREET APPROXIMATELY 230 FEET NORTH OF THE CENTER LINE OF CENTRAL AVENUE. ELEVATION 738.01

CONTROL POINTS

C.P. #	NORTHING	EASTING	STATION	OFFSET
#1 X-CUT IN WALK SET	1891936.086	1070351.013	101+15.76	32.65' RT
#2 5/8" IR W/ CAP SET	1892839.314	1070246.814	110+23.08	31.30' LT
#3 X-CUT IN WALK SET	1893450.499	1070287.600	116+32.38	32.14' RT
#4 5/8" IR W/ CAP SET	1892923.011	1070306.321	111+04.49	31.30' RT
#5 5/8" IR W/ CAP SET	1892289.589	1070270.204	104+72.87	28.54' LT
#6 X-CUT IN WALK FOUND	1892176.980	1070254.126	103+62.11	49.31' LT
#7 X-CUT IN WALK SET	1892544.426	1070241.049	107+28.62	48.12' LT
#8 5/8" IR W/ CAP SET	1893045.303	1070234.736	112+29.38	35.65' LT
#9 5/8" IR W/ CAP SET	1893226.715	1070297.413	114+08.32	33.79' LT
#10 X-CUT IN WALK SET	1892469.459	1069970.056	106+63.86	321.73' LT
#11 X-CUT IN WALK SET	1892490.122	1070243.387	106+74.26	47.82' LT

REVISIONS

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

ALIGNMENT, TIES AND BENCHMARKS

MAIN STREET

STA. 100+55 TO STA. 123+85.90

SCALE IN FEET

DATE: 11/26/07
DESIGNED BY: SJC
CHECKED BY: JRV