

F.A.U. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0285	01-00052-00-FP	WILL	71	04
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 83956

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	LANDSCAPE	DRAINAGE	SIGNALS	TRAINING	LOCAL AGENCY
S.I. CODE NO.	PAY ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE							
				1000-2A	SFTY-1D	Y003	Y007	Y031-1F	Y080	CITY OF LOCKPORT	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	652	652							
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	318	318							
20100500	TREE REMOVAL, ACRES	ACRE	0.9	0.9							
20101200	TREE ROOT PRUNING	EACH	30				30				
20200100	EARTH EXCAVATION	CU YD	16367	16367							
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1637	1637							
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1637	1637							
20800150	TRENCH BACKFILL	CU YD	5050					2150			2900
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	27923				27923				
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	90	90							
25000210	SEEDING, CLASS 2A	ACRE	2				2				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	393				393				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	393				393				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	393				393				
25100630	EROSION CONTROL BLANKET	SQ YD	7566				7566				
25200110	SODDING, SALT TOLERANT	SQ YD	20357				20357				
25200200	SUPPLEMENTAL WATERING	UNIT	40				40				
28000300	TEMPORARY DITCH CHECKS	EACH	6				6				
28000510	INLET FILTERS	EACH	42				42				
28100101	STONE RIPRAP, CLASS A1	SQ YD	39				39				
28100107	STONE RIPRAP, CLASS A4	SQ YD	39				39				
28200200	FILTER FABRIC	SQ YD	30				30				
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	1791	1791							
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	912	912							
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	11217	11217							
40600300	AGGREGATE (PRIME COAT)	TON	18	18							
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	178	178							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	189	189							
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2080	2080							
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	312	312							
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	986	986							
40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SQ YD	16959	16959							
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	117	117							
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	850	850							
42400800	DETECTABLE WARNINGS	SQ FT	88	88							
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2840	2840							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1252	1252							
44000600	SIDEWALK REMOVAL	SQ FT	950	950							
48101498	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	1392	1392							
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	16					16			
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1					1			
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1					1			
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1					1			
54214713	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	EACH	2					2			
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	1					1			
54247180	GRATING FOR CONCRETE FLARED END SECTION 42"	EACH	1					1			
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	134					134			
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	692					692			
55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	252					252			
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	722					722			
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	140					140			
55022500	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 42"	FOOT	426					426			

\* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

151ST STREET IMPROVEMENT  
SUMMARY OF QUANTITIES

SCALE: VERT. N/A  
HORIZ. N/A  
DATE: 11-21-07  
DRAWN BY: RG  
CHECKED BY: JMN