

F.A.U. RITE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0285	01-00052-00-FP	WILL	71	05
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 83956

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	LANDSCAPE	DRAINAGE	SIGNALS	TRAINING	LOCAL AGENCY
S.I.	CODE NO.	PAY ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE						NON-PARTICIPATING
					I000-2#	SFTY-1D	Y003	Y007	Y031-IF	Y080	CITY OF LOCKPORT
	55023700	STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	511					511		
	55023800	STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	937					937		
	55023900	STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	97					97		
	55024100	STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	1253					1253		
	55024500	STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 36"	FOOT	576					576		
	55034200	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 23, RISE 14	FOOT	192					192		
	55100500	STORM SEWER REMOVAL 12"	FOOT	252					252		
	55100700	STORM SEWER REMOVAL 15"	FOOT	1128					1128		
	55101200	STORM SEWER REMOVAL 24"	FOOT	159					159		
	55101300	STORM SEWER REMOVAL 27"	FOOT	31					31		
	56400100	FIRE HYDRANTS TO BE MOVED	EACH	2							2
	60107600	PIPE UNDERDRAINS 4"	FOOT	108					108		
	60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1					1		
	60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	2					2		
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	35					35		
	60203905	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1					1		
	60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1					1		
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	10					10		
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	12					12		
	60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	2					2		
	60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6							6
	60500060	REMOVING INLETS	EACH	2					2		
	60600095	CLASS SI CONCRETE (OUTLET)	CU YD	2					2		
	60600605	CONCRETE CURB, TYPE B	FOOT	55					55		
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	7424					7424		
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9						
	67100100	MOBILIZATION	L SUM	1	1						
	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1						
	70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1						
	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1						
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4032		4032					
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6400		6400					
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3477		3477					
*	72000100	SIGN PANEL - TYPE 1	SQ FT	172		172					
*	72000200	SIGN PANEL - TYPE 2	SQ FT	25		25					
	72900200	METAL POST, TYPE B	FOOT	312		312					
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	656		656					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18788		18788					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1370		1370					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	321		321					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	290		290					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	297		297					
*	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	24		24					
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	315					315		
*	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	76					76		
*	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	20					20		
*	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	39					39		
*	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	402					402		
*	81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	41					41		
*	81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	35					35		
*	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	165					165		

\* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE
JAK	12-7-07
IDOT COMMENTS	12-20-07

ILLINOIS DEPARTMENT OF TRANSPORTATION

151ST STREET IMPROVEMENT  
SUMMARY OF QUANTITIES

SCALE: VERT. N/A  
HORIZ. N/A

DATE 11-21-07

DRAWN BY RG  
CHECKED BY JMN