

SUMMARY OF QUANTITIES

CODE NO	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY (000)
20200100	EARTH EXCAVATION	CU YD	961	961
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	150	150
20400800	FURNISHED EXCAVATION	CU YD	200	200
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	150	150
20800150	TRENCH BACKFILL	CU YD	3	3
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	200	200
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	2043	2043
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	36	36
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	36	36
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	36	36
25200110	SODDING, SALT TOLERANT	SQ YD	2043	2043
25200200	SUPPLEMENTAL WATERING	UNIT	10	10
28000510	INLET FILTERS	EACH	19	19
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	5263	5263
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2651	2651
40600300	AGGREGATE (PRIME COAT)	TON	12	12
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	361	361
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	32	32
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N60	TON	645	645
40701841	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8"	SQ YD	4940	4940
42001300	PROTECTIVE COAT	SQ YD	10605	10605
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4000	4000
42400800	DETECTABLE WARNINGS	SQ FT	450	450
44000100	PAVEMENT REMOVAL	SQ YD	7787	7787
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	7251	7251
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	745	745
44000600	SIDEWALK REMOVAL	SQ FT	4000	4000
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500	500
44002208	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2"	SQ YD	280	280
44003100	MEDIAN REMOVAL	SQ FT	462	462
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	70	70
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	70	70
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	70	70
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	70	70
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	12	12
60107600	PIPE UNDERDRAINS 4"	FOOT	250	250
60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	2	2
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	1	1
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	3384	3384
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	2917	2917
60624600	CORRUGATED MEDIAN	SQ FT	462	462

* SPECIALTY ITEM

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY (1,000)
67100100	MOBILIZATION	L SUM	1	1
70102650	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL-MO	2	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	260	260
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	40	40
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	4463	4463
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	608	608
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	50	50
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	170	170
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	87	87
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	261	261
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4463	4463
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	608	608
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	50	50
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	170	170
81603065	UNIT DUCT, 600V, 2-1C NO. 2, 1/2" NO. 2 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	500	500
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	20	20
84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	1	1
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1	1
88600100	DETECTOR LOOP, TYPE I	FOOT	205	205
89502200	MODIFY EXISTING CONTROLLER	EACH	1	1
X4023000	TEMPORARY ACCESS (ROAD)	EACH	8	8
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), L-4.75, N50	TON	158	158
XX003303	CONCRETE LIGHT POLE	EACH	1	1
XX003885	IRRIGATION SYSTEM	L SUM	1	1
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	2	2
Z0017700	DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED	EACH	16	16
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	1	1
Z0019600	DUST CONTROL WATERING	UNIT	5	5
A2000116	TREE, ACER X FREEMANI AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	8	8
A2008124	TREE, TILIA CORDATA GREENSPIRE (GREENSPIRE LITTLE LEAF LINDEN), 3" CALIPER, BALLED AND BURLAPPED	EACH	7	7
B0026574	TREE, PYRUS CALLERYANA AUTUMN BLAZE (AUTUMN BLAZE CALLERY PEAR), 10' HEIGHT, BALLED AND BURLAPPED	EACH	8	8

REVISIONS	
NAME	DATE

URS 100 S. WACKER DR., SUITE 500 TEL: (312) 939-1000
CHICAGO IL, 60606 FAX: (312) 939-4198

VILLAGE OF WOODRIDGE
JANES AVENUE
71ST STREET TO LORRAINE AVENUE
REHABILITATION AND RESURFACING
SUMMARY OF QUANTITIES

SCALE: 1" = 400'
DATE: 11/30/2007
DRAWN BY: VAP
CHECKED BY: DDL