

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	06-00314-00-RS	PEORIA	19	4
FED. ROAD DIST. NO.	ILLINOIS	CONTRACT # 89455		

Item Number	Items	Unit	Quantity
21400100*	GRADING AND SHAPING DITCHES	LF	56
25000300	SEEDING CLASS 3	ACRE	0.37
25000400	NITROGEN FERT NUTR	POUND	33.7
25000500	PHOSPHORUS FERT NUTR	POUND	33.7
25000600	POTASSIUM FERT NUTR	POUND	33.7
25100115	MULCH METHOD 2	ACRE	0.37
25100630	EROSION CONTROL BLANKET	SQ YD	189
28000500	INLET & PIPE PROTECTION	EACH	14
28100500	BROKEN CONC RIPRAP	SQ YD	84
35100100	AGG BASE CSE A	TON	114.3
35800100	PREPARATION OF BASE	SQ YD	1338
35800200	AGGREGATE BASE REPAIR	TON	305
40600100	BIT MATLS PR CT	GAL	1327
40600400	MIX CR JTS FLANGWAYS	TON	3.2
40600515	LEV BIND HM N30	TON	20
40600615	LEV BIND MM N30	TON	89
40600982	HMA SURF REM BUTT JT	SQ YD	117
40603080	HMA BC IL-19.0 N50	TON	230
40603305	HMA SC "C" N30	TON	1265
44000085*	HMA SUR REMOVAL (CM) SPL	SQ YD	2432
44000500	COMB CURB GUTTER REM	LF	893
542C0217	PIPE CULVERTS, CL C 1 12	LF	42
54213663	PRC FLAR END SEC 18"	EACH	6
54213675	PRC FLAR END SEC 30"	EACH	2
54213867	STEEL END SECTION 12"	EACH	2
550A0040	STORM SEW CL A 1 10"	LF	12
550A0090	STORM SEW CL A 1 18"	LF	395
60218400	MANHOLE TA 4 DIA T1F CL	EACH	1
60236700	INLETS TA T10 F&G	EACH	17
60602500	CONCRETE GUTTER TYPE A	LF	523
60602800	CONCRETE GUTTER TYPE B	LF	1170
60603300*	GUTTER OUTLET	EACH	6
60623714*	CONCRETE MEDIAN (SPECIAL)	SQ FT	12
67100100*	MOBILIZATION	L SUM	1
70102620	TR CONT & PROT 701501	L SUM	1
X0301245*	SHOULDER REMOVAL	SQ YD	117
X2113010*	FURNISHING & PLACING TOP SOIL	CU YD	200
Z0013798*	CONSTRUCTION LAYOUT	L SUM	1

1000

REVISIONS			
NO.	DATE	DESCRIPTION	APPROVED

DESIGNED AJS
 DRAWN AJS, KSB, JLA
 CHECKED EEA
 DATE 01/04/08



SUMMARY OF QUANTITIES

