

REMOVAL ITEMS									
LOCATION (STA TO STA)	LENGTH (FT)	WIDTH (FT)	SHOULDER REMOVAL (SY)	SURF REM BUTT JT (SY)	HMA SUR RM (CM)SPL*	COMB CURB GUTTER REM (LF)	GRADING & SHP DITCH (LF)		
ROSE HILL DR	0+00 TO 0+10	10	25					27.8	
	0+00 TO 4+83	523	2	116.2					
	18+80 TO 18+90	10	12						
ROSE HILL SUBTOTALS				116.2	41.1	0.0	0.0	0.0	
MEMORIAL LANE	0+50 TO 0+60	10	16					17.8	
	5+75 TO 10+50	475	17.5						923.6
	10+25 RT	8							8
	10+40 RT	8							8
	10+50 RT	8							8
	10+55 RT	8							8
	10+70 RT	8							8
	10+75 RT	8							8
	11+90 TO 13+40 LT	160							160
	14+50 TO 16+15 RT	165							165
	21+90 TO 22+00	10	16					17.8	
MEMORIAL SUBTOTALS				0.0	35.6	923.6	373.0	0.0	
HERVEY LIGHTNER DR	3+00 TO 3+10	10	18					20.0	
	6+10 LT	10							10
	8+75 RT	10							10
	9+05 RT	10							10
	11+60 TO 16+50 LT	490							490
	11+60 TO 19+30 LT	770	2						171.1
	16+25 TO 17+00								
	24+40 TO 24+50	10	18					20	
HERVEY LIGHTNER SUBTOTALS				0.0	40.0	171.1	520.0	56.0	
DEMOLITION TOTALS				116.2	116.7	1094.7	893.0	56.0	

*NOTE: SEE PATCHING SCHEDULE FOR ADDITIONAL BIT SURFACE REMOVAL IN THE PATCHING AREAS.

PATCHING SCHEDULE										
LOCATION (STATION)	LENGTH (FT)	WIDTH (FT)	HMA SUR RM (CM) SPL (SY)	PREPARATION OF BASE (SY)	AGG BASE REPAIR (TON)	BIT MATLS PR CT APPRATE=0.3 GAL/SY (GAL)	HMA BC IL-19.0 N50 (TON)			
ROSE HILL DR	3+05 RT	10	5	5.6	5.6	1.3	1.7	0.5		
	4+60	55	12	73.3	73.3	16.7	22.0	6.3		
	5+10 LT	30	3	10.0	10.0	2.3	3.0	0.9		
	5+85	50	12	66.7	66.7	15.2	20.0	5.8		
	7+92 RT	8	5	4.4	4.4	1.0	1.3	0.4		
	8+10 RT	20	5	11.1	11.1	2.5	3.3	1.0		
	8+55	45	12	60.0	60.0	13.7	18.0	5.2		
	9+90 LT	20	3	6.7	6.7	1.5	2.0	0.6		
	11+55 RT	10	3	3.3	3.3	0.8	1.0	0.3		
	12+50	60	12	80.0	80.0	18.2	24.0	6.9		
	14+10	50	5	27.8	27.8	6.3	8.3	2.4		
	14+75 RT	15	3	5.0	5.0	1.1	1.5	0.4		
	ROSE HILL SUBTOTALS				353.9	353.9	80.6	106.2	30.5	
	MEMORIAL LANE	0+00 RT	39.5	3.5	15.4	15.4	3.5	4.6	1.3	
0+05 RT		16.5	10	18.3	18.3	4.2	5.5	1.6		
0+35 LT		19.5	3.5	7.6	7.6	1.7	2.3	0.7		
3+00		65.5	16.5	120.1	120.1	27.4	36.0	10.4		
3+90 RT		28	13	40.4	40.4	9.2	12.1	3.5		
4+60 RT		16.5	3.5	6.4	6.4	1.5	1.9	0.6		
5+00 LT		26.5	5	14.7	14.7	3.4	4.4	1.3		
5+10 RT		49	3.5	19.1	19.1	4.3	5.7	1.6		
5+65 LT		6.5	3.5	2.5	2.5	0.6	0.8	0.2		
11+50 LT		255	8	226.7	226.7	51.6	68.0	19.6		
12+30 RT		75	5	41.7	41.7	9.5	12.5	3.6		
13+60 RT		102	2.5	28.3	28.3	6.5	8.5	2.4		
14+15 LT		75	5	41.7	41.7	9.5	12.5	3.6		
14+95 RT		15	3.5	5.8	5.8	1.3	1.8	0.5		
15+20 RT	40	5	22.2	22.2	5.1	6.7	1.9			
MEMORIAL LANE SUBTOTALS				610.9	610.9	139.2	183.3	52.7		
HERVEY LIGHTNER DR	4+00	50	4	22.2	22.2	5.1	6.7	1.9		
	5+00	35	18	70.0	70.0	15.9	21.0	6.0		
	6+00 LT	20	6	13.3	13.3	3.0	4.0	1.2		
	6+00 RT	30	4	13.3	13.3	3.0	4.0	1.2		
	7+75	40	8	35.6	35.6	8.1	10.7	3.1		
	8+00	15	18	30.0	30.0	6.8	9.0	2.6		
	8+25	30	8	26.7	26.7	6.1	8.0	2.3		
	10+50	25	15	41.7	41.7	9.5	12.5	3.6		
	12+00	42	4	18.7	18.7	4.3	5.6	1.6		
	16+25	50	8	44.4	44.4	10.1	13.3	3.8		
17+00	60	8	53.3	53.3	12.1	16.0	4.6			
19+00	10	3	3.3	3.3	0.8	1.0	0.3			
HERVEY LIGHTNER SUBTOTALS				372.6	372.6	84.9	111.8	32.1		
PATCHING TOTALS				1337.4	1337.4	304.6	401.2	115.3		

PAVING SCHEDULE											
LOCATION (STA TO STA)	LENGTH (FT)	WIDTH (FT)	AGG BSE CSE A, 8" THICK (TON)	BIT MATLS PR CT APP RATE = 0.08 GAL/SY (GAL)	MIX CR JTS FLANGES (TON)	LEV BIND HM N30 (TON)	LEV BIND MM N30 (TON)	HMA BC IL- 19.0 N50 (TON)	HMA SC "C" N30 (TON)		
ROSE HILL DR	0+00 TO 18+90	1890	12	201.6	0.8				289.8		
	0+10 TO 0+35	60	25	76.3							
	0+50 TO 4+83	433	VAR				75				CROWN CORRECTION WEDGE
	4+25 TO 5+15	90	12				13.8				
ROSE HILL SUBTOTALS				76.3	201.6	0.8	0.0	88.8	0.0	289.8	
MEMORIAL LANE	0+50 TO 22+00	2150	16	305.8	1.1				480.8		
	5+75 TO 10+50	475	17.5	73.9					79.7		
	10+25 TO 16+15	373	2	37.9							
	15+95 TO 17+50	155	17.5						34.7		
MEMORIAL SUBTOTALS				37.9	379.7	1.1	0.0	0.0	114.3	480.8	
HERVEY LIGHTNER DR	3+00 TO 24+50	2150	18	344	1.3				494.5		
	11+60 TO 19+30 LT	770	2			19.7					
HERVEY LIGHTNER SUBTOTALS				0.0	344.0	1.3	19.7	0.0	0.0	494.5	
PAVEMENT TOTALS				114.3	925.3	3.2	19.7	88.8	114.3	1265.1	

REVISIONS			
NO.	DATE	DESCRIPTION	APPROVED

DESIGNED AJS
DRAWN AJS, KSB, JLA
CHECKED EEA
DATE 01/04/08



SCHEDULES-PAVEMENT & DEMO

SPRINGDALE CEMETERY
3014 N. PROSPECT RD.
PEORIA, ILLINOIS
FOUNDED 1854
REBORN 2003

P:\3160070016\DWG\Final Set\QUANTITY SCHEDULES_1.dwg, 1/4/2008 11:22:23 AM, \peoria-m\peoria-p5