

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
MS 7660	05-00104-00-RS	TAZEWELL	36	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE 1000
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
20201550	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	439
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	439
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	60
28000510	INLET FILTERS	EACH	8
35101400	AGGREGATE BASE COURSE, TYPE B	TON	230
35300200	PORTLAND CEMENT CONCRETE BASE COURSE 7"	SQ YD	212
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	20
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.9
40600300	AGGREGATE (PRIME COAT)	TON	5
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	6
40600990	TEMPORARY RAMP	SQ YD	76
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	282
40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SQ YD	4640
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	4
42001300	PROTECTIVE COAT	SQ YD	853
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	152
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	721
44000100	PAVEMENT REMOVAL	SQ YD	4640
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	2360
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1012
44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	3849
60107600	PIPE UNDERDRAIN 4"	FOOT	295
60241800	INLETS, TYPE G-1	EACH	5
60260100	INLETS TO BE ADJUSTED	EACH	1
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	3777
67100100	MOBILIZATION	L SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	36
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	803
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	83
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	130
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	52
XX005238	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	CU YD	70
Z0004500	BITUMINOUS DRIVEWAY PAVEMENT, 8"	SQ YD	232
Z0013798	CONSTRUCTION LAYOUT	L. SUM	1
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	5

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**MULLER ROAD IMPROVEMENTS
SUMMARY OF QUANTITIES**

SCALE: AS SHOWN
DATE 11-14-07

DRAWN BY: DLC
CHECKED BY: KMC