

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
MS 7660	05-00104-00-RS	TAZEWELL	36	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LOCATION		DRIVEWAY PAVEMENT REMOVAL SQ YD	
RT. STA. 11+00.1		31.67	
LT. STA. 12+39.6		8.22	
RT. STA. 12+40.3		39.78	
LT. STA. 13+02.9		21.44	
RT. STA. 13+05.6		48.78	
RT. STA. 13+65.9		24.56	
LT. STA. 13+94.3		16.56	
LT. STA. 14+76.6		22.67	
RT. STA. 15+24.9		21.56	
LT. STA. 15+36.3		20.33	
LT. STA. 15+90.9		13.44	
RT. STA. 16+41.5		18.78	
LT. STA. 16+18.0	TO	LT. STA. 17+35.0	90.67
		RT. STA. 17+00.7	21.89
		LT. STA. 17+89.4	13.89
		LT. STA. 18+35.0	23.89
		RT. STA. 18+61.6	23.67
		RT. STA. 18+86.4	15.22
		LT. STA. 18+88.0	23.56
LT. STA. 19+29.7	TO	LT. STA. 20+00.0	49.11
		RT. STA. 19+65.7	19.33
LT. STA. 20+00.0	TO	LT. STA. 21+20.0	62.11
		RT. STA. 20+24.9	20.67
		LT. STA. 21+36.4	21.44
		RT. STA. 21+36.4	12.89
		RT. STA. 22+16.3	15.78
		LT. STA. 22+61.8	23.56
		RT. STA. 22+63.9	16.44
LT. STA. 23+37.0	TO	LT. STA. 25+00.0	90.89
LT. STA. 25+00.0	TO	LT. STA. 25+30.0	16.56
		LT. STA. 25+46.8	23.00
		LT. STA. 26+17.7	24.11
		LT. STA. 26+91.7	20.22
		LT. STA. 27+79.5	21.33
		RT. STA. 27+91.7	14.67
		RT. STA. 28+51.1	16.00
		LT. STA. 28+63.2	21.56
		RT. STA. 29+15.5	20.78
SUBTOTAL		1,011.03	
TOTAL		1,012	

LOCATION	TEMPORARY RAMP SQ YD
STA. 10+35.00	23.70
STA. 26+25.00	23.70
STA. 29+50.00	28.20
SUBTOTAL 75.60	
TOTAL 76	

LOCATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL CU YD	SUB-BASE GRANULAR MATERIAL, TYPE B CU YD
STA. 14+20 TO STA. 16+40	130.00	130.00
STA. 10+35 TO STA. 23+40	309.00	309.00
SUBTOTAL 439.00		439.00
TOTAL 439		439

LOCATION	INLETS TO BE ADJUSTED EACH
STA. 16+75.50	1.00
TOTAL 1	

LOCATION	COMBINATION CURB AND GUTTER REMOVAL FOOT
STA. 10+35.00 TO STA. 15+00.00 LT	465.00
STA. 10+35.00 TO STA. 15+00.00 RT	465.00
STA. 15+00.00 TO STA. 20+00.00 LT	500.00
STA. 15+00.00 TO STA. 20+00.00 RT	500.00
STA. 20+00.00 TO STA. 25+00.00 LT	500.00
STA. 20+00.00 TO STA. 25+00.00 RT	500.00
STA. 25+00.00 TO STA. 29+60.00 LT	460.00
STA. 25+00.00 TO STA. 26+05.00 RT	121.00
STA. 26+45.00 TO STA. 29+65.00 RT	338.00
SUBTOTAL 3,849.00	
TOTAL 3,849	

LOCATION	TRAFFIC CONTROL AND PROTECTION L SUM
ENTIRE PROJECT	1
TOTAL 1	

LOCATION	INLETS, TYPE G-1 (WITH VANE GRATES) EACH	FLOW DIRECTION
STA. 13+45.00	1.00	RT
STA. 13+45.50	1.00	LT
STA. 16+73.00	1.00	LT
STA. 21+62.50	1.00	RT
STA. 21+62.50	1.00	LT
TOTAL 5		

LOCATION	PORTLAND CEMENT CONCRETE BASE COURSE 7" SQ YD
LT. STA. 23+40 TO LT. STA. 29+50	105.00
RT. STA. 23+40 TO RT. STA. 29+67	107.00
SUBTOTAL 212.00	
TOTAL 212	

LOCATION	PROTECTIVE COAT SQ YD
STA. 10+35.00 TO STA. 15+00.00 LT	103.3
STA. 10+35.00 TO STA. 15+00.00 RT	103.3
STA. 15+00.00 TO STA. 20+00.00 LT	111.1
STA. 15+00.00 TO STA. 20+00.00 RT	111.1
STA. 20+00.00 TO STA. 25+00.00 LT	111.1
STA. 20+00.00 TO STA. 25+00.00 RT	111.1
STA. 25+00.00 TO STA. 29+50.00 LT	100.0
STA. 25+00.00 TO STA. 26+05.00 RT	26.9
STA. 26+45.00 TO STA. 29+65.00 RT	75.1
SUBTOTAL 853.0	
TOTAL 853.0	

LOCATION	TEMPORARY EROSION CONTROL SEEDING POUND
STA. 10+35 TO STA. 29+50	60.0
SUBTOTAL 60.0	
TOTAL 60	

LOCATION	PAVEMENT REMOVAL SQ YD
STA. 10+35 TO STA. 23+40	4,640.00
SUBTOTAL 4,640.00	
TOTAL 4,640	

LOCATION	DRAINAGE STRUCTURE TO BE REMOVED EACH
STA. 13+45.50	1.00
STA. 13+45.50	1.00
STA. 16+73.50	1.00
STA. 21+62.50	1.00
STA. 21+62.50	1.00
SUBTOTAL 5.00	
TOTAL 5	

LOCATION	AGGREGATE BASE COURSE, TYPE B TON
LT. & RT. STA. 10+35 TO LT. & RT. STA. 23+40	230.0
SUBTOTAL 230.0	
TOTAL 230	

LOCATION	MOBILIZATION L SUM
ENTIRE PROJECT	1
SUBTOTAL 1	
TOTAL 1	

LOCATION	CONSTRUCTION LAYOUT L SUM
ENTIRE PROJECT	1
TOTAL 1	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

MULLER ROAD IMPROVEMENTS SCHEDULE OF QUANTITIES

SCALE: AS SHOWN
DATE 11-14-07

DRAWN BY: DLC
CHECKED BY: KMC