



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 21, 2008

SUBJECT: FAU 8694 (Washington St.)  
Project M-5022(009)  
Section 06-00045-00-BR (Fairfield)  
Wayne County  
Contract No. 95526  
Item 52  
March 7, 2008 Letting  
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

**Plans – Sheet 2.**

**Proposal – Schedule of Prices, Index of Special Provisions and page 11 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric Harm  
Interim Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger  
Engineer of Project Development  
and Implementation

COUNTY NAME	CODE	DIST	SECTION NUMBER	PROJECT NUMBER	ROUTE
WAYNE	191	07	06-00045-00-BR FAIRFIELD	M-5022/009/000	FAU 8694

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
20200100	EARTH EXCAVATION	CU YD	32.000 X				
20300100	CHANNEL EXCAV	CU YD	54.000 X				
20400800	FURNISHED EXCAV	CU YD	265.000 X				
25000900	SEEDING CL 1 SPL	ACRE	0.500 X				
28100807	STONE DUMP RIP CL A4	TON	71.000 X				
30200650	PROCESS MOD SOIL 12	SQ YD	1,946.000 X				
30201500	LIME	TON	49.000 X				
40200800	AGG SURF CSE B	TON	50.000 X				
42000300	PCC PVT 8	SQ YD	1,636.000 X				
42001200	PAVEMENT FABRIC	SQ YD	1,636.000 X				
42300200	PCC DRIVEWAY PAVT 6	SQ YD	94.000 X				
42400100	PC CONC SIDEWALK 4	SQ FT	2,507.000 X				
42400500	PC CONC SIDEWALK SPL	SQ FT	1,706.000 X				
42400800	DETECTABLE WARNINGS	SQ FT	50.000 X				
44000100	PAVEMENT REM	SQ YD	878.000 X				

Revised 2-21-2008

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
44000200	DRIVE PAVEMENT REM	SQ YD	81.000 X	=			
44000500	COMB CURB GUTTER REM	FOOT	533.000 X	=			
44000600	SIDEWALK REM	SQ FT	441.000 X	=			
44004400	PAVT REMOVAL SPL	SQ YD	1,200.000 X	=			
50100100	REM EXIST STRUCT	EACH	1.000 X	=			
50300100	FLOOR DRAINS	EACH	3.000 X	=			
50800205	REINF BARS, EPOXY CTD	POUND	89,900.000 X	=			
50900500	ALUM RAILING	FOOT	198.000 X	=			
51500100	NAME PLATES	EACH	1.000 X	=			
54003000	CONC BOX CUL	CU YD	414.400 X	=			
55019500	SS 1 RCP CL 4 12	FOOT	208.000 X	=			
55019600	SS 1 RCP CL 4 15	FOOT	104.000 X	=			
55100500	STORM SEWER REM 12	FOOT	206.000 X	=			
55100700	STORM SEWER REM 15	FOOT	18.000 X	=			
59300100	CONTR LOW-STRENG MATL	CU YD	743.400 X	=			

Revised 2-21-2008

FAU 8694  
 06-00045-00-BR FAIRFIELD  
 WAYNE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT NUMBER - 95526

ECMS002 DTGECM03 ECMR003 PAGE 3  
 RUN DATE - 02/20/08  
 RUN TIME - 210703

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
60100905	PIPE DRAINS 4	FOOT	20.000 X				
60235300	INLETS TA T1F CL	EACH	2.000 X				
60236800	INLETS TA T11F&G	EACH	7.000 X				
60240215	INLETS TB T1F CL	EACH	2.000 X				
60255500	MAN ADJUST	EACH	2.000 X				
60500060	REMOV INLETS	EACH	8.000 X				
60605000	COMB CC&G TB6.24	FOOT	926.000 X				
63000005	SPBGR TY B	FOOT	50.000 X				
63200305	SPBGR REM	FOOT	237.000 X				
67000500	ENGR FIELD OFFICE B	CAL MO	6.000 X				
67100100	MOBILIZATION	L SUM	1.000 X				
70101700	TRAF CONT & PROT	L SUM	1.000 X				
70102640	TR CONT & PROT 701801	L SUM	1.000 X				
72000100	SIGN PANEL T1	SQ FT	6.000 X				
72900200	METAL POST TY B	FOOT	26.000 X				

Revised 2-21-2008

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
78003100	PREF PL PM TB LTR-SYM	SQ FT	24.000 X	=	=	=	=
78003110	PREF PL PM TB LINE 4	FOOT	110.000 X	=	=	=	=
78003150	PREF PL PM TB LINE 12	FOOT	374.000 X	=	=	=	=
78003180	PREF PL PM TB LINE 24	FOOT	39.000 X	=	=	=	=
				TOTAL	\$		

- NOTE:
1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
  2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
  3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
  4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

*Revised 2-21-2008*

INDEX OF SPECIAL PROVISIONS

<u>SHEET NO.</u>	<u>ITEM</u>
1	REFERENCES
2	DESCRIPTION OF WORK
2	SAW CUTTING
2	UTILITIES
2	LOCATING UNDERGROUND UTILITIES
2	MODIFIED SOILS
3	STRUCTURE EXCAVATION
3	PAVEMENT REMOVAL SPECIAL
3	SEEDING CLASS I SPECIAL
3	SIGNS & POSTS
4	PIPE DRAINS 4"
4	AGGREGATE SURFACE COURSE, TYPE B
4	GUARDRAIL REMOVAL
4	P.C. CONCRETE SIDEWALK (SPECIAL)
5	TRAFFIC CONTROL PLAN
6-7	TRAFFIC CONTROL MAP - STAGE 1
7-8	TRAFFIC CONTROL MAP - STAGE 2
10	UTILITIES
<del>11</del>	<del>ELECTRIC CABLE</del>
<del>11</del>	<del>ELECTRIC UTILITY SERVICE CONNECTION</del>
<del>11</del>	<del>LIGHT POLE FOUNDATIONS</del>
<del>11</del>	<del>LIGHT POLE SPECIAL</del>
12	CORPS OF ENGINEERS PERMIT

Revised 2-21-2008

ELECTRIC CABLE

Material shall be No. 10 THHN Stranded Copper.

ELECTRIC UTILITY SERVICE CONNECTION

This work will consist of connecting the electric cables into the existing breaker box. This work shall be coordinated with the city of Fairfield Electric Department.

For bidding purposes, this item shall be estimated as \$200.00.

LIGHT POLE FOUNDATIONS

Foundations shall be constructed in accordance with Art. 836.03(a) of the Standard Specifications and as shown on the plans. This work will be paid for at the contract unit price per each for Light Pole Foundations.

LIGHT POLE, SPECIAL

This work shall be done in accordance with the applicable parts of section 830 of the Standard Specifications. Light Poles shall be 10' height Holophane North Yorkshire Extruded Shaft 17", or equal. Luminaire shall be Utility Granville type No. HOLOGVU175MHMTB5RPBHG-LP or equal.

Revised 2-21-2008