


STA 55 + 55
EXISTING STRUCTURE NO. 087-3018
 THREE SPAN TIMBER DECK ON STEEL STRINGERS WITH
 CLOSED TIMBER ABUTMENTS, TIMBER WINGWALLS AND
 TIMBER PILE BENT PILES
 129' - 0" BK - BK OF ABUTMENT

STA 55 + 57.94
PROPOSED STRUCTURE NO. 087-3546
 3 SPAN PPC DECK BEAM BRIDGE
 181' - 10 1/2" BK - BK ABUTMENT
 24' - 0" FACE TO FACE OF RAIL
 SKEW = 30° RT FWD

RALPH And AUDREY CHAMBERLAIN
 Parcel No. 001

TY L. And DARLENE DAGEN
 Parcel No. 002



BM/2 = Nail in Corner Wooden
 Fence Post. Elev. +544.45

Note:
 The channel shall be excavated with 2:1 slopes at
 right angles to the channel within the limits of the
 proposed structure and transitioned to meet the
 existing channel at the proposed R.O.W. line
 Quantity = 1726 Cu.Yd.
 Est. qty. used for embankment = 863 Cu.Yd.

