

MODEL: SQQ [Sheet]
FILE NAME: c:\pw\work\pwr\hille\ad0977188\U774C96-ant-SQQ.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				EFFINGHAM COUNTY	EFFINGHAM COUNTY
				BRIDGE	ROADWAY
				0047	0047
				025-6004	URBAN
44200050	WELDED WIRE REINFORCEMENT	SQ YD	812.7		812.7
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	169.5		169.5
44200962	CLASS B PATCHES, TYPE III, 9 INCH	SQ YD	269.1		269.1
44200964	CLASS B PATCHES, TYPE IV, 9 INCH	SQ YD	374.1		374.1
44201298	DOWEL BARS 1 1/4"	EACH	958		958
44213200	SAW CUTS	FOOT	2470		2470
44213204	TIE BARS 3/4"	EACH	270		270
50102400	CONCRETE REMOVAL	CU YD	88.7	88.7	
50157300	PROTECTIVE SHIELD	SQ YD	825	825	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	88.1	88.1	
50300300	PROTECTIVE COAT	SQ YD	212	212	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	10460	10460	
50800515	BAR SPLICERS	EACH	36	36	
50800530	MECHANICAL SPLICERS	EACH	14	14	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				EFFINGHAM COUNTY	EFFINGHAM COUNTY
				BRIDGE	ROADWAY
				0047	0047
				025-6004	URBAN
52000110	PREFORMED JOINT STRIP SEAL	FOOT	154	154	
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.5	0.5
70107005	PAVEMENT MARKING BLACKOUT TAPE, 5"	FOOT	2056	2056	
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	42	21	21
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	856.8	856.8	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1412.5	1412.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1212.5	1212.5	
70600240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2	1.5	0.5
70600340	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 2	EACH	1	0.5	0.5
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	745	745	
* 78004620	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LINE 4"	FOOT	2790	312	2478
* 78004630	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LINE 6"	FOOT	560	60	500

* SPECIALTY ITEM

1 REVISED 2-20-2025
REV - MS

	USER NAME = jessica.hille	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					328A	(1X-1)BJR, BDR	EFFINGHAM	30	3
		CHECKED -	REVISED -		CONTRACT NO. 74C96							
	PLOT DATE = 10/31/2024	DATE -	REVISED -		SCALE:	SHEET 1	OF 2	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	