

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 90% FEDERAL 10% STATE 0004				
20101000	TEMPORARY FENCE	FOOT	140	140				
20200100	EARTH EXCAVATION	CU YD	2490	2490				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	130	130				
20400800	FURNISHED EXCAVATION	CU YD	775	775				
20800150	TRENCH BACKFILL	CU YD	11.8	11.8				
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	2990	2990				
21400100	GRADING AND SHAPING DITCHES	FOOT	1219	1219				
25000210	SEEDING, CLASS 2A	ACRE	2	2				
25000312	SEEDING, CLASS 4A	ACRE	0.1	0.1				
25000314	SEEDING, CLASS 4B	ACRE	0.2	0.2				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	158	158				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	158	158				
25100630	EROSION CONTROL BLANKET	SO YD	7440	7440				
28000305	TEMPORARY DITCH CHECKS	FOOT	60	60				
28000400	PERIMETER EROSION BARRIER	FOOT	803	803				
28000510	INLET FILTERS	EACH	3	3				

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 90% FEDERAL 10% STATE 0004				
28100203	STONE RIPRAP, CLASS A2	TON	240	240				
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	130	130				
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	4190	4190				
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	780	780				
35501317	HOT-MIX ASPHALT BASE COURSE, 8 1/4"	SO YD	2165	2165				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8	8				
40600300	AGGREGATE (PRIME COAT)	TON	40	40				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	9	9				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), [L-4, 75, N50	TON	393	393				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	83	83				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	19	19				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	88	88				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	625	625				
44000100	PAVEMENT REMOVAL	SO YD	561	561				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	6002	6002				

FILE NAME: c:\work\p1010101\p1010101\p1010101.dwg	USER NAME: mdy/ja	DESIGNED: -	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US 121L 59 AT FOX LAKE RD SUMMARY OF QUANTITIES	F.A.P. RTE. 334	SECTION 106N-1	COUNTY LAKE	TOTAL SHEETS 39	SHEET NO. 3
PLOT SCALE: 1/8" = 1'-0"	CHECKED: -	REVISED: -	CONTRACT NO. 60T50							
PLOT DATE: 10/19/2012	DATE: -	REVISED: -	FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT							
SCALE: 1" = 100'	SHEET NO. 1 OF 3 SHEETS	STA. TO STA.								