

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0005 90% FED 10% STATE	TRAFFIC SIGNAL 0021 90% FED 5% STATE 5% CITY OF HARVEY	EVP 0021 100% CITY OF HARVEY	INTER CONNECT 0021 90% FED 10% STATE			CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0005 90% FED 10% STATE	TRAFFIC SIGNAL 0021 90% FED 5% STATE 5% CITY OF HARVEY	EVP 0021 100% CITY OF HARVEY	INTER CONNECT 0021 90% FED 10% STATE			
81400100	HANDHOLE	EACH	6		6					87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT	FOOT	518		518					
											GROUNDING CONDUCTOR, NO. 6 1C									
81400200	HEAVY-DUTY HANDHOLE	EACH	2		2					87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL	EACH	2		2					
											15 FT.									
81400300	DOUBLE HANDHOLE	EACH	1		1					87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL	EACH	2		2					
											16 FT.									
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL	EACH	2				2			87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24	EACH	1		1					
	INSTALLATION										FT.									
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1					87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34	EACH	2		2					
											FT.									
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO.	FOOT	4516				4516			87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36	EACH	1		1					
	14 1C										FT.									
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.	FOOT	427		427					87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16		16					
	14 2C																			
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.	FOOT	728.5		455	273.5				87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4					
	14 3C																			
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.	FOOT	1029.5		1029.5					87800400	CONCRETE FOUNDATION, TYPE E 30-INCH	FOOT	10		10					
	14 5C										DIAMETER									
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.	FOOT	1344.5		1344.5					87800415	CONCRETE FOUNDATION, TYPE E 36-INCH	FOOT	33		33					
	14 7C										DIAMETER									
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO.	FOOT	1157.5		1157.5					87900200	DRILL EXISTING HANDHOLE	EACH	1					1		
	14 1 PAIR																			
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO.	FOOT	35.5		35.5															
	6 2 C																			

1

FILE NAME : USER NAME : gullmount
 c:\p\work\p\l\gullmount\p\0301142\p\3009-Desig\p
 PLOT SCALE : 1000000 / 1" = 1M
 PLOT DATE : 12/21/2012

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -
 REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

**Specialty Hems*

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.
 397 104TS-1112) COOK 39 5
 CONTRACT NO. 60T92
 ILLINOIS FED. AID PROJECT

REV. 2-20-13