

REMOVE SILT WHEN BAG IS HALF FULL OR MORE OFTEN IF RECOMMENDED BY THE MAUNFACUTURER. DISPOSE OF SILT BY TRANSPORTING THE FILLED BAG TO DISPOSAL AREA. SLIT THE BAG, BLEND SILT INTO EXISTING TOPOGRAPHY, SEED AND MULCH

MAINTAIN EXTRA FILTER BAGS ON SITE. REPLACE DAMAGED BAGS PROMPTLY.

TYPICAL FLOW RATE: 10 GPM x W x L

FIGURE S1. SEDIMENT FILTER BAG

NOTE: DEWATERING SYSTEM DETAILS SHALL BE USED IN CONJUCTION WITH THE PROJECT SPECIAL PROVISIONS.

GR@EF***	W. Higgins Road: Suite 280 Chicago, Illinois 60631 (773) 399-0112	

	USER NAME = 1485	DESIGNED	-		REVISED	-
80		DRAWN	-		REVISED	-
	PLOT SCALE = 40.0000 '/ in.	CHECKED	-		REVISED	-
	PLOT DATE = 12/11/2012	DATE	-	12-20-2012	REVISED	-

STATE OF ILLINOIS					
DEPARTMENT OF TRANSPORTATION					

Ī	WILLOW	ROAD OVER DES PLAINES RIVER RIPRAP IMPROVEMENTS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
١		DEWATERING SYSTEM DETAILS	330	2012-068 I	соок	15	12
ļ	DEVVAIENING STSTEIN DETAILS				CONTRACT	NO. 6	OV73
ı	SCALE:	SHEET 2 OF 3 SHEETS STA. TO STA.		ILLINOIS FED. AI	D PROJECT		