INDEX OF SHEETS

1.	TITLE SHEET
2.	INDEX OF SHEETS AND GENERAL NOTES
3.-4.	LOCATION MAP AND INTERSECTIONS NUMBERS
5.-10.	SUMMARY OF QUANTITIES
11.-16.	DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN DETALS

TRAFFIC SIGNAL PLANS

PAGE *	TS *	INTERSECTION NAME
17.	6043	U.S. 20 AT GREENBRIAR DRIVE
18.	11105	U.S. 20 AT SWIFT ROAD
19.	12513	U.S. 20 AT MARCUS CINEMA DRIVE
20.	12505	U.S. 20 AT LOMBARD ROAD / FOXDALE ROAD
21.	12500	U.S. 20 AT ITASCA ROAD
22.	12510	U.S. 20 AT MILL ROAD
23.	12515	U.S. 20 AT JOHN F. KENNEDY DRIVE
24.	6020	U.S. 20 AT ADDISON ROAD
25.	6070	U.S. 20 AT WOOD DALE ROAD / VILLA AVENUE
26.	6015	U.S. 20 AT IL 83 WEST RAMP (A&B)
27.	6495	IL 64 AT WESTWOOD AVENUE / LINCOLN AVENUE
28.	12520	IL 53 AT FULLERTON AVENUE / COLLINS AVENUE
29.	6378	IL 59 AT APPLE VALLEY DRIVE
30.	6377	IL 59 AT STRUCKMAN BOULEVARD
31.	6379	IL 59 AT WOODLAND HILLS PARKWAY
32.	22125	IL 59 AT SCHICK ROAD
33.	6160	IL 19 AT SPRUCE AVENUE
34.	6140	IL 19 AT MARSHALL ROAD
35.	12065	IL 19 AT CHURCH ROAD
36.	610	IL 83 AT MARK STREET
37.	650	IL 83 AT THORNDALE AVENUE
38.	590	IL 83 AT FOSTER AVENUE
39.	600	IL 83 AT HILLSIDE DRIVE
40.	595	IL 83 AT GROVE AVENUE / SHERWOOD DRIVE
41.	545	IL 83 AT THIRD AVENUE
42.	6085	U.S. 20 AT ROSEDALE AVENUE
43.	4600	U.S. 20 AT BLOOMINGDALE ROAD
44.	4610	U.S. 20 AT SPRINGBROOK CENTER / SUNRISE DRIVEWAY
45.	4595	U.S. 20 AT FAIRFIELD WAY
46.	4605	U.S. 20 AT CIRCLE DRIVE
47.	6037	U.S. 20 AT EUCLID DRIVE / LAKEVIEW DRIVE
48.	6035	U.S. 20 AT GLEN ELLYN ROAD
49.	6045	U.S. 20 AT MEDINAH ROAD
50.	12376	IL 64 AT FAIR OAKS ROAD / ANCIENT OAKS ROAD
51.	6425	IL 64 AT COUNTY FARM ROAD
52.	6445	IL 64 AT KUHN ROAD
53.	6435	IL 64 AT GARY AVENUE
54.	6465	IL 64 AT SCHMALE ROAD
55.	21395	IL 64 AT PRESIDENT STREET / FIRESIDE DRIVE
56.	6420	IL 64 AT BLOOMINGDALE ROAD
57.	11390	IL 64 AT GLENDALE SQUARE MENARD'S
58.	6450	IL 64 AT GLEN ELLYN ROAD / MAIN STREET
59.	21910	U.S. 20 AT ELGIN / O'HARE EXPRESSWAY RAMP "D"
60.	13770	U.S. 20 AT GREENBROOK BOULEVARD
61.	7870	U.S. 20 AT BARTELS ROAD / ARLINGTON DRIVE
62.	6163	IL 19 AT CATALPA AVENUE
63.	6164	IL 19 AT BLOOMINGDALE ROAD
64.	6456	IL 64 AT LOMBARD ROAD
65.	6455	IL 64 AT MAIN STREET - LOMBARD
66.	6440	IL 64 AT GRACE STREET
67.	12320	IL 38 AT FINLEY ROAD
68.	12325	IL 38 AT MAIN STREET
69.	14065	IL 38 AT HIGHLAND AVENUE
70.	11180	IL 38 AT FAIRFIELD ROAD
71.	11415	IL 38 AT LOMBARD SHOPPING CENTER
72.	6310	IL 56 AT FAIRFIELD AVENUE
73.	21870	IL 56 AT TECHNOLOGY DRIVE / MAXANT DRIVE
74.	6293	IL 56 AT FOUNTAIN SQUARE DRIVE
75.	22135	IL 53 AT SIDNEY AVENUE
76.	6215	IL 53 AT IL 64
77.	6235	IL 53 AT ST. CHARLES ROAD
78.	9037	IL 19 AT LAWRENCE AVENUE
79.	9100	IL 19 AT MAPLE AVENUE
80.	6145	IL 19 AT MEDINAH ROAD
81.	6030	U.S. 20 AT GARY AVENUE
82.	7875	U.S. 20 AT BRYN MAWR AVENUE
83.	22025	U.S. 20 AT RODENBURG ROAD
84.	6065	U.S. 20 AT SPRINGFIELD DRIVE
85.	6365	IL 59 AT ARMY TRAIL ROAD
86.	6366	IL 59 AT SMITH ROAD
87.	12375	IL 64 AT PRINCE CROSSING
88.	6185	IL 38 AT KRESS ROAD
89.	6175	IL 38 AT FABYAN PARKWAY / WASHINGTON STREET
90.	6180	IL 38 AT JOLIET STREET
91.	22115	IL 59 AT DIVERSEY PARKWAY
92.	6355	IL 64 AT IL 59
93.	22110	IL 59 AT INGLATON AVENUE
94.	8853	IL 59 AT HAWTHORNE LANE
95.	8850	IL 59 AT JAMES AVENUE
96.	6390	IL 59 AT FOREST AVENUE
97.	12020	IL 59 AT JOLIET STREET / EDGEWOOD WALK
98.	6170	IL 19 AT PROSPECT AVENUE
99.	15090	IL 19 AT ADDISON ROAD
100.-103.	15100	IL 19 AT WOOD DALE ROAD

GENERAL NOTES

THE ILLINOIS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", JANUARY 1, 2012; MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS, LATEST EDITION; PROJECT SPECIFICATIONS; ALL APPLICABLE REQUIREMENTS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION; THE CITIES OF JOLIET AND LOCKPORT; THE VILLAGE OF CHANNAHON, FRANKFORT, PLAINFIELD, AND ROMEOVILLE; THE WILL COUNTY DEPARTMENT OF HIGHWAYS; ALL APPLICABLE REQUIREMENTS OF THE ORDINANCES OF AUTHORITIES HAVING JURISDICTION; AND ALL ADDENDA THERETO SHALL GOVERN THIS WORK.

THE STANDARD SPECIFICATIONS, PROJECT SPECIFICATIONS, CONSTRUCTION PLANS, AND SUBSEQUENT DETAILS ARE ALL TO BE CONSIDERED AS PART OF THE CONTRACT. INCIDENTAL ITEMS OR ACCESSORIES NECESSARY TO COMPLETE THIS WORK MAY NOT BE SPECIFICALLY NOTED BUT ARE TO BE CONSIDERED A PART OF THE CONTRACT.

WHENEVER, DURING CONSTRUCTION OPERATIONS, ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF GUTTERS, DRAINAGE STRUCTURES, DITCHES, ETC. SUCH THAT THE NATURAL FLOW LINE OF WATER IS OBSTRUCTED, THE LOOSE MATERIAL WILL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES AND FLOW LINES SHALL BE FREE FROM DIRT AND DEBRIS. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR'S FAILURE TO PROVIDE THE ABOVE WILL PRECLUDE ANY POSSIBLE ADDED COMPENSATION REQUESTED DUE TO DELAYS OF UNSTABLE MATERIALS CREATED AS A RESULT THEREOF.

THE CONTRACTOR SHALL SOLEY BE RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ADEQUATE SIGNS, TRAFFIC CONTROL DEVICES, AND WARNING DEVICES TO INFORM AND PROTECT THE PUBLIC DURING ALL PHASES OF CONSTRUCTION.

THE CONTRACTOR IS RESPONSIBLE FOR RETURNING ALL AREAS AFFECTED BY EQUIPMENT OR LABORERS TO EXISTING CONDITIONS. THE CONTRACTOR IS ALSO RESPONSIBLE FOR PROTECTING ALL NEW WORK UNTIL COMPLETION OF THIS CONTRACT.

EXISTING UTILITIES: WHEN THE PLANS OR SPECIAL PROVISIONS INCLUDE INFORMATION PERTAINING TO THE LOCATION OF UNDERGROUND UTILITY FACILITIES. SUCH INFORMATION IS BASED ON RECORD INFORMATION PROVIDED BY THE INDIVIDUAL UTILITY OWNERS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES. THE CONTRACTOR SHALL ALSO CONTACT J.U.L.I.E. TO OBTAIN LOCATES OF THE RESPECTIVE UTILITY COMPANIES UNDERGROUND FACILITIES.

RESTORATION OF WORK AREA: RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC. AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC, SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD IN ACCORDANCE TO STANDARD SPECIFICATIONS ARTICLE 252 WHICH SHALL INCLUDE THE REQUIRED WATERING PER ARTICLE 252.08. ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS ARTICLE 250 AND 251, RESPECTIVELY.

THE GENERAL CONTRACTOR IS REQUIRED TO HIRE AN ENVIRONMENTAL FIRM WITH AT LEAST FIVE (5) DOCUMENTED LEAKING UNDERGROUND STORAGE TANK CLEANUPS OR THAT IS PRE-QUALIFIED IN HAZARDOUS WASTE BY THE DEPARTMENT TO REMEDIATE THE SOIL CONTAMINATION AND MONITOR FOR WORKER PROTECTION.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION. THIS SHALL INCLUDE LOCATING THE MAST ARM FOUNDATIONS AND VERIFYING THE MAST ARM LENGTH.

THE EXACT LOCATION OF ALL UTILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR BEFORE ORDERING ANY MATERIALS AND STARTING ANY WORK. FOR LOCATIONS OF UTILITIES, LOCALLY OWNED EQUIPMENT, LEASED ENFORCEMENT CAMERA SYSTEM FACILITIES, AND IDOT UNDERGROUND FACILITIES, CONTACT THE LOCAL COUNTIES, MUNICIPALITIES, AND IDOT FOR LOCATES. THE CONTRACTOR SHALL CALL 'JULIE' AT (800) 892-0123 OR 811, IN THE CITY OF CHICAGO CONTACT DIGGER AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED UTILITIES (48 HOURS NOTIFICATION REQUIRED).

THE CONTRACTOR SHALL CHECK THE PROPOSED TRAFFIC SIGNAL EQUIPMENT LOCATIONS FOR OVERHEAD UTILITY CONFLICTS. THE CONTRACTOR SHALL COORDINATE ANY CONFLICTS WITH THE UTILITY COMPANIES AND THE RESIDENT ENGINEER BEFORE ORDERING MATERIALS.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, LOCAL GOVERNMENT AGENCIES, AND IDOT.

THE CONTRACTOR SHALL RELOCATE ANY EXISTING SIGN PANELS FROM PAINTED POSTS THAT ARE INDICATED FOR REPLACEMENT TO A NEW POST AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER. THE COST OF REMOVAL, RELOCATION, AND ANY NEW MOUNTING HARDWARE NECESSARY TO COMPLETE THIS WORK SHALL BE INCLUDED IN THE PAY ITEM OF THE LENGTH AS SPECIFIED IN THE PLANS.

THE CONTRACTOR SHALL REPLACE BROKEN MOUNTING BRACKETS AT ALL RETOFIT SIGNAL HEAD INTERSECTIONS OR AS DIRECTED BY THE ENGINEER. THE COST OF THIS WORK SHALL BE INCLUDED IN THE CORRESPONDING SIGNAL HEAD, LED, RETROFIT PAY ITEM OF THE TYPE AND NUMBER OF SIGNAL HEADS, FACES, AND SECTIONS AS SPECIFIED IN THE PLANS.

DUE TO THE PRESENCE OF A RED LIGHT CAMERA RUNNING (RLR) CAMERA RUNNING FOR THE BELOW LOCATIONS, THE CONTRACTOR SHALL NOTIFY THE MUNICIPALITY AND RLR CAMERA COMPANY PRIOR TO THE START OF CONSTRUCTION. THE MUNICIPALITY OR THE RLR CAMERA COMPANY SHALL MAKE THE CAMERA INOPERABLE FOR THE TIME OF CONSTRUCTION. ANY RLR CAMERA EQUIPMENT THAT IS IN CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED BY ITS RESPECTIVE OWNERS PRIOR TO THE START OF CONSTRUCTION.

RLR CAMERA LOCATION:

TS 12515 - U.S. 20 (LAKE ST) AT JOHN F. KENNEDY JR. DRIVE
TS 6020 - U.S. 20 (LAKE ST) AT ADDISON ROAD

VILLAGE OF ADDISON 1 FRIENDSHIP PLAZA ADDISON, IL 60101 (630) 543-4100	RED SPEED ILLINOIS, LLC 400 EISENHOWER LANE NORTH LOMBARD, IL 60148 (630) 317-5700

TS 6445 - IL 64 (NORTH AV) AT KUHN ROAD
TS 6435 - IL 64 (NORTH AV) AT GARY AVENUE

VILLAGE OF CAROL STREAM 500 NORTH GARY AVENUE CAROL STREAM, IL 60188 (630) 665-7050	REDFLEX TRAFFIC SYSTEM 23751 W. 23RD AVENUE, STE 15 PHOENIX, AZ 85085 (623) 207-2000

TS 6175 - IL 38 (ROOSEVELT RD) AT FABYAN PARKWAY / WASHINGTON STREET
TS 6355 - IL 64 (NORTH AV) AT IL 59

VILLAGE OF WEST CHICAGO 475 MAIN STREET WEST CHICAGO, IL 60186 (630) 293-2200	RED SPEED ILLINOIS, LLC 400 EISENHOWER LANE NORTH LOMBARD, IL 60148 (630) 317-5700

TS 6366 - IL 59 AT SMITH ROAD

VILLAGE OF WAYNE 5N 430 RAILROAD AVENUE WAYNE, IL 60184 (630) 584-3090	RED SPEED ILLINOIS, LLC 400 EISENHOWER LANE NORTH LOMBARD, IL 60148 (630) 317-5700

TS 6030 - U.S. 20 AT GARY AVENUE

VILLAGE OF ROSELLE 31 S. PROSPECT ST ROSELLE, IL 60172 (630) 980-2000	RED SPEED ILLINOIS, LLC 400 EISENHOWER LANE NORTH LOMBARD, IL 60148 (630) 317-5700

RAILROAD REQUIREMENTS AT IL RTE 19 AND WOOD DALE ROAD

METRA WILL NOT REQUIRE RAILTOAD PROTECTIVE LIABILTY INSURANCE (RPLI) FROM THE CONTRACTOR ON THIS CONTRACT.

THE CONTRACTOR WILL BE REQUIRED TO PROVIDE A COPY OF THEIR GENERAL LIABILITY INSURANCE.

THE CONTRACTOR WILL BE REQUIRED TO APPLY AND PAY FOR A RIGHT-OF-ENTRY (ROE) PERMIT AND SECURE FLAGGING SERVICES WHEN WORKING ON METRA'S RIGHT-OF-WAY. THE FEE FOR THE ROE PERMIT IS NOT REIMBURSABLE TO THE CONTRACTOR. THE FLAGGING SERVICES SHALL BE PAID FOR BY THE CONTRACTOR AND THE CONTRACTOR SHALL BE REIMBURSED FOR THE COST IN ACCORDANCE WITH SECTION 109.05 OF THE STANDARD SPECIFICATIONS.