

SUMMARY OF QUANTITIES (CONTD.)

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	MCDOT			JOHNSBURG	
				ROADWAY 80% FEDERAL 20% LOCAL 0004	RETAINING WALL 80% FEDERAL 20% LOCAL 0040	SIGNALS/LIGHTING 80% FEDERAL 20% LOCAL 0021	ITEP 80% FEDERAL 20% LOCAL 0031	VILLAGE OF JOHNSBURG 100% LOCAL 0043
50900805	PEDESTRIAN RAILING	FOOT	6	6				
54010402	PRECAST CONCRETE BOX CULVERTS 4' X 2'	FOOT	208	208				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	6	6				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2				
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	1	1				
54213672	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 27"	EACH	2	2				
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1				
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2				
54213699	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54"	EACH	1	1				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	904	904				
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	194	194				
550A0130	STORM SEWERS, CLASS A, TYPE 1 27"	FOOT	238	238				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1,293	1,293				
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	417	417				
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1,296	1,296				
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	144	144				
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	221	221				
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	325	325				
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	125	125				
550A0680	STORM SEWERS, CLASS A, TYPE 3 18"	FOOT	25	25				
550A0730	STORM SEWERS, CLASS A, TYPE 3 30"	FOOT	95	95				
550A0790	STORM SEWERS, CLASS A, TYPE 3 54"	FOOT	657	657				
55100400	STORM SEWER REMOVAL 10"	FOOT	47	47				
55100500	STORM SEWER REMOVAL 12"	FOOT	193	193				
55100700	STORM SEWER REMOVAL 15"	FOOT	285	285				
55100900	STORM SEWER REMOVAL 18"	FOOT	222	222				
55101100	STORM SEWER REMOVAL 21"	FOOT	316	316				
55101200	STORM SEWER REMOVAL 24"	FOOT	497	497				
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	352	352				

* SPECIALTY ITEM

COMPANY NAME: HRGreen
 PROJECT CONTACT: HRGreen.com
 DATE PLOTTED: 1/3/2013 9:27:53 AM
 FILE NAME: 080622-sum.dgn
 PLOT NUMBER: 001-00-00-00-00-00
 PLOT DATE: 1/3/2013



USER NAME = spornal	DESIGNED - JRM	REVISED -
FILE NAME = 080622-sum.dgn	DRAWN - JPA	REVISED -
PLOT SCALE = N.T.S.	CHECKED - TH	REVISED -
PLOT DATE = 1/3/2013	DATE - 1/3/13	REVISED -

**MCHENRY COUNTY
DIVISION OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 3 OF 8 SHEETS STA. TO STA.

F.A.U. RTE. 168	SECTION 05-00314-00-WR	COUNTY MCHENRY	TOTAL SHEETS 187	SHEET NO. 6
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63515	