

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0005	0005	0005	0021	0021	0021	0021	0021	0021	0021	0031	0031	0031	0031
				RECONSTRUCTION, NO CAPACITY ADDED	SYSTEM PRESERVATION, RESURFACING	SYSTEM PRESERVATION, RESURFACING	SYSTEM PRESERVATION, RESURFACING	SAFETY (TRAFFIC SIGNALS)	SAFETY (TRAFFIC SIGNALS)	SAFETY (TRAFFIC SIGNALS)	SAFETY (SW / BP)	SAFETY (SW / BP)	SAFETY (SW / BP)	SAFETY (LIGHTING)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	NON-PARTICIPATING
				HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD	HOLMES WAY	BARRINGTON ROAD / SCHAUMBURG ROAD	BARRINGTON ROAD / HOLMES WAY	INTERCONNECT	HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD		HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	758	33	395	275	55											
20101000	TEMPORARY FENCE	FOOT	3680	320	2080	880	400											
20101100	TREE TRUNK PROTECTION	EACH	92	8	52	22	10											
X 20101200	TREE ROOT PRUNING	EACH	92	8	52	22	10											
X 20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	73	7	41	15	10											
X 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	19	1	11	7												
20200100	EARTH EXCAVATION	CU YD	11778	1042	6333	4046	357											
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	550	75	250	200	25											
20400800	FURNISHED EXCAVATION	CU YD	1917	65	981	761	110											
20800150	TRENCH BACKFILL	CU YD	1736	99	1584		53											
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1185	170	650	325	40											
X 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	11865												1325	5743	4797	
X 21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	273															273
X 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	150												16	71	63	
X 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	150												16	71	63	
X 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	150												16	71	63	
X 25200110	SODDING, SALT TOLERANT	SQ YD	12166												1325	5743	5098	
X 25200200	SUPPLEMENTAL WATERING	UNIT	182												20	86	76	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	251	12	119	105	15											
28000400	PERIMETER EROSION BARRIER	FOOT	3528	120	3110	298												
28000510	INLET FILTERS	EACH	220	10	116	84	10											
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	550	75	250	200	25											
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	17653	1729	10024	5426	474											
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	229		147	82												
31101180	SUBBASE GRANULAR MATERIAL, TYPE B 2"	SQ YD	4777	142	778	1392	133				376	1397	559					
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1389	388	689	285	27											
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	96		36	60												
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	7962		5192	2770												
35301300	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	1447		1085	362												
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	269				269											
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	179		179													
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	10263	1099	5931	2744	489											
40600300	AGGREGATE (PRIME COAT)	TON	54	5	30	14	2											
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40		15	15	10											
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	104		104													
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1310		1310													

X SPECIALTY ITEM