

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0005	0005	0005	0021	0021	0021	0021	0021	0021	0021	0031	0031	0031	NON-PARTICIPATING
				RECONSTRUCTION, NO CAPACITY ADDED	SYSTEM PRESERVATION, RESURFACING	SYSTEM PRESERVATION, RESURFACING	SYSTEM PRESERVATION, RESURFACING	SAFETY (TRAFFIC SIGNALS)	SAFETY (TRAFFIC SIGNALS)	SAFETY (TRAFFIC SIGNALS)	SAFETY (SW / BP)	SAFETY (SW / BP)	SAFETY (SW / BP)	SAFETY (LIGHTING)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	
				HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD	HOLMES WAY	BARRINGTON ROAD / SCHAUMBURG ROAD	BARRINGTON ROAD / HOLMES WAY	INTERCONNECT	HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD		HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD	
40600895	CONSTRUCTING TEST STRIP	EACH	2		1	1												
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	115		97		18											
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	537			537												
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	511				511											
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	5884		4000	1884												
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	169		20		149											
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4249		2904	1345												
40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	1569	1569														
42001200	PAVEMENT FABRIC	SQ YD	178				178											
42001300	PROTECTIVE COAT	SQ YD	12523	337	5320	4145	318				390	1430	583					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	20985								3382	12571	5032					
42400800	DETECTABLE WARNINGS	SQ FT	646								129	298	219					
44000100	PAVEMENT REMOVAL	SQ YD	7106	1520	3651	1768	167											
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1506				1506											
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	24055		24055													
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	3447		1637	1655	155											
44000300	CURB REMOVAL	FOOT	250	14	79	157												
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	14657	624	8909	4311	813											
44000600	SIDEWALK REMOVAL	SQ FT	18535	1476	11263	5051	745											
44000100	MEDIAN REMOVAL	SQ FT	13754		7882	5872												
44200956	CLASS B PATCHES, TYPE I, 10 INCH	SQ YD	53				53											
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	265				265											
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	371				371											
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	371				371											
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	66		58		8											
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	330		292		38											
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	462		409		53											
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	471		418		53											
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	19419				19419											
45200100	JOINT OR CRACK ROUTING (PC CONCRETE PAVEMENT AND SHOULDER)	FOOT	50179		31519		18660											
45200300	JOINT OR CRACK FILLING	POUND	11761		7387		4374											
550A0040	STORM SEWERS, CLASS A, TYPE 1 10"	FOOT	6		6													
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	349	52	175	51	71											
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	2				2											
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	509	135	129	236	9											
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	5				5											

X SPECIALTY ITEM