

LOWES ENTRANCE							
STATION	DISTANCE	CUT	FILL	CUT	FILL	CUT	FILL
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. YD.)	(CU. YD.)
500+75.	25	36.2	10.0	35.1	10.2	32.5	9.5
501+00.	50	34.1	10.5	31.1	8.7	57.5	16.1
501+50.	50	28.1	6.9	26.3	5.3	48.7	9.9
502+00.	13.78	24.6	3.8	23.2	3.7	11.8	1.9
502+13.78		21.7	3.7				
LOWES ENTRANCE - TOTAL						150.6	37.4
BARRINGTON ROAD - TOTAL						6,332.6	981.4

FILE NAME =
...oad\sheet\2329_Schedule.02.dgn

USER NAME = djk

DESIGNED - JAT

REVISED -

DRAWN - JAT

REVISED -

PLOT SCALE = 50,000' / 1" =

CHECKED - DJK

REVISED -

PLOT DATE = 8/16/2012

DATE - 8-20-12

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SHEET NO. 5 OF 9 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1322	01-00074-00-CH	COOK	245	28
CONTRACT NO. 63629				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-CMM-80030501				