SCHAUMBURG ROAD - STAGE 3							
STATION	DISTANCE	CUT	FILL	CUT	FILL	CUT	FILL
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. YD.)	(CU. YD.)
STATION	DISTANCE	CUT	FILL	CUT	FILL	CUT	FILL
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. YD.)	(CU. YD.)
35+19.5		3.7	0.0				
	30.5			2.8	0.0	3.1	0.0
35+50		1.8	0.0				
	50			0.9	0.0	1.7	0.0
36+00.		0.0	0.0				
	50			3.0	0.0	5.6	0.0
36+50		6.0	0.0				
	50			6.8	0.0	12.6	0.0
37+00		7.6	0.0				
	50			8.4	0.0	15.6	0.0
37+50		9.2	0.0				
	50			8.0	0.0	14.8	0.0
38+00		6.8	0.0				
	50			7.8	0.0	14.4	0.0
38+50		8.8	0.0				
	50			9.4	0.0	17.4	0.0
39+00		10.0	0.0				
	50			11.2	0.0	20.7	0.0
39+50		12.3	0.0				
	50			13.0	0.0	24.1	0.0
40+00		13.7	0.0				
	50			13.1	0.0	24.3	0.0
40+50		12.5	0.0				
	50			12.4	0.0	23.0	0.0
41+00		12.3	0.0				
	50			11.9	0.0	22.0	0.0
41+50		11.5	0.0				
	50			7.6	0.0	14.1	0.0
42+00		3.7	0.0				
43+50		3.8	0.0				
	50			4.9	0.0	9.1	0.0
44+00		6.0	0.0				
	50			6.0	0.0	11.1	0.0
44+50		6.0	0.0				
	50			6.4	0.0	11.8	0.0
45+00		6.8	0.0				
	50			7.7	0.0	14.2	0.0
45+50		8.5	0.0				
	50			9.1	0.0	16.9	0.0
46+00		9.8	0.0				
	50			10.2	0.0	18.8	0.0
46+50		10.6	0.0				
	50			10.8	0.0	20.1	0.0
47+00		11.1	0.0				
	50			10.1	0.0	18.7	0.0
47+50		9.1	0.0				
	50			10.7	0.0	19.8	0.0
48+00		12.3	0.0				
	50			6.1	0.0	11.3	0.0
48+50		0.0	0.0				
	50			0.0	0.0	0.0	0.0
49+00		0.0	0.0				
	50			3.0	0.0	5.6	0.0
49+50		6.1	0.0				
	50			6.0	0.0	11.1	0.0
50+00		5.9	0.0				
	50			6.2	0.0	11.6	0.0
50+50		6.6	0.0				
	50			14.2	0.0	26.3	0.0

(CONTINUED) SCHAUMBURG ROAD - STAGE 3							
STATION	DISTANCE	CUT	FILL	CUT	FILL	CUT	FILL
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. YD.)	(CU. YD.)
51+00.		21.8	0.0				
	50			27.9	0.0	51.6	0.0
51+50.		33.9	0.0				
	50			38.5	0.0	71.3	0.0
52+00.		43.1	0.0				
	50			30.7	1.2	56.8	2.3
52+50.		18.2	2.5				
	50			14.7	1.2	27.2	2.3
53+00.		11.1	0.0				
	40			13.3	0.0	19.7	0.0
53+40.03		15.5	0.0				
SCHAUMBURG ROAD - STAGE 3 TOTAL						626.7	4.6

SCHAUMBURG ROAD - TOTAL	4,046.2	760.6

FILE NAME = ...\cad\sheet\2329_Schedule_02.dgn	USER NAME = djk	DESIGNED - JAT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - JAT	REVISED -			1322	01-00074-00-CH	COOK	245	31
	PLOT SCALE = 50.0000 ' / in.	CHECKED - DJK	REVISED -						CONTRACT NO. 63629	
	PLOT DATE = 8/17/2012	DATE - 8-20-12	REVISED -		SHEET NO. 8 OF 9 SHEETS	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	M-CMM-8003(051)	