

SUMMARY OF QUANTITIES

0028

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
1	20100110 TREE REMOVAL (6-15 UNITS DIAMETER)	UNIT	72
2	20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18
3	20101000 TEMPORARY FENCE	FOOT	2,000
4	20101200 TREE ROOT PRUNING	EACH	20
5	20101300 TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	10
6	20101350 TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	15
7	20200100 EARTH EXCAVATION	CU YD	3,272
8	20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,253
9	20800150 TRENCH BACKFILL	CU YD	36
10	21001000 GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	7,539
11	21101625 TOPSOIL FURNISH AND PLACE 6"	SQ YD	3,750
12	25000210 SEEDING, CLASS 2A	ACRE	2
13	25000400 NITROGEN FERTILIZER NUTRIENT	POUND	220
14	25000500 PHOSPHORUS FERTILIZER NUTRIENT	POUND	220
15	25000600 POTASSIUM FERTILIZER NUTRIENT	POUND	220
16	25100630 EROSION CONTROL BLANKET	SQ YD	11,857
17	25200200 SUPPLEMENTAL WATERING	UNIT	90
18	28000250 TEMPORARY EROSION CONTROL SEEDING	POUND	245
19	28000400 PERIMETER EROSION BARRIER	FOOT	2,000
20	28000510 INLET FILTER	EACH	5
21	30300001 AGGREGATE SUBGRADE IMPROVEMENT	CU YD	1,253
22	35102000 AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	7,539
23	40600100 BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,427
24	40603335 HOT-MIX ASPHALT, SURFACE COURSE, MIX "D" N50	TON	1,159
25	42400200 PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,091
26	42400800 DETECTABLE WARNINGS	SQ FT	196
27	44000100 PAVEMENT REMOVAL	SQ YD	1050
28	44000161 HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	720
29	44000200 DRIVEWAY PAVEMENT REMOVAL	SQ YD	755
30	44000500 COMBINATION CURB AND GUTTER REMOVAL	FOOT	890
31	44000600 SIDEWALK REMOVAL	SQ FT	16,450
32	50105220 PIPE CULVERT REMOVAL	FOOT	90
33	54213657 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	9
35	550A2320 STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	396

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
36	55100500 STORM SEWER REMOVAL 12"	FOOT	50
37	56109100 TAPPING VALVES AND SLEEVES 12"	EACH	1
38	56400100 FIRE HYDRANTS TO BE MOVED	EACH	4
39	56400500 FIRE HYDRANTS TO BE REMOVED	EACH	5
40	56400820 FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	5
41	56500600 DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	1
42	60207605 CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1
43	60240301 INLETS, TYPE B, TYPE 8 GRATE	EACH	1
44	60246900 VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
45	60260300 INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1
46	60266600 VALVE BOXES TO BE ADJUSTED	EACH	1
47	60603800 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,595
48	67100100 MOBILIZATION	L SUM	1
49	70102620 TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
50	70102635 TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
51	70102640 TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
52	72000100 SIGN PANEL - TYPE 1	SQ FT	54.5
53	72900100 METAL POST - TYPE A	FOOT	20
54	72900200 METAL POST - TYPE B	FOOT	100
55	78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	910
56	78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	505
57	78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	778
58	78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	100
59	78300100 PAVEMENT MARKING REMOVAL	SQ FT	20
60	A2001716 TREE, ACER SACCHARUM (SUGAR MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	9
61	X00291024 WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	5
62	X0327008 REMOVE AND RELOCATE SIGN (SPECIAL)	EACH	1
63	X4230710 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH, SPECIAL	SQ YD	80
64	X8950090 RELOCATE EXISTING CONTROLLER BOX	EACH	1
65	XX000714 FENCE TO BE REMOVED AND RE-ERECTED	FOOT	200
66	Z0004534 HOT-MIX ASPHALT DRIVEWAY PAVEMENT 9"	SQ YD	615
67	Z0013798 CONSTRUCTION LAYOUT	L SUM	1
68	Z0017400 DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	25
69	Z0017700 DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED	EACH	2
70	Z0077900 WOOD POST AND RAIL FENCE	FOOT	229

* Indicates specialty items
 ^ Indicates special provision

PLAN	DATE
NO.	BY
NO.	BY
NO.	BY

PROFILE	DATE
NO.	BY
NO.	BY
NO.	BY

ENGINEERING RESOURCE ASSOC., INC.
 CONSULTING ENGINEERS, SURVEYORS & SURVEYORS
 150 WEST AVENUE, SUITE 150
 WILMINGTON, MASSACHUSETTS 01890
 PHONE (650) 394-3060 FAX (650) 395-2152

FILE NAME =	USER NAME =
C:\West Chicago\100810.00 Dike Trail	erborner
Connector\CAD\Font Design\00810 Summary	DESIGNED - BD
Quantities.dwg	DRAWN - RT
	CHECKED - JFM
	PLGT DATE = 1/15/2013
	DATE - APRIL, 2012

DESIGNED - BD	REVISION - 01-14-2013
DRAWN - RT	REVISION -
CHECKED - JFM	REVISION -
DATE - APRIL, 2012	REVISION -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 1 SHEETS

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	00-00064-00-BT		31	3
FED. ROAD DIST. NO. 1 ILLINOIS			CONTRACT NO. 63730	