

SUMMARY OF QUANTITIES

PAY ITEM #	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				0004	0011	0021	0031	0042	
* 78006100	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	692			692			
* 78200300	PRISMATIC CURB REFLECTOR	EACH	16			16			
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	5			5			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	4,473			4,473			
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	87			87			
* 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	92			92			
* 85000300	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	L SUM	1			1			
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,396			1,396			
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,465			1,465			
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	120			120			
* 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	4			4			
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	20			20			
* 87900200	DRILL EXISTING HANDHOLE	EACH	7			7			
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	6			6			
* 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1			1			
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	8			8			
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1			
* A2000086	TREE, ACER X FREEMANI ARMSTRONG (ARMSTRONG FREEMAN MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	8					8	
* A2000320	TREE, ACER MIYABEI MORTON (STATE STREET MIYABE MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	10					10	
* A2002502	TREE, CARPINUS BETULUS FASTIGIATA (COLUMNAR EUROPEAN HORNBEAM), 3" CALIPER, BALLED AND BURLAPPED	EACH	5					5	
* A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5					5	
* A2005420	TREE, LIRIODENDRON TULIPIFERA (TULIP TREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	7					7	
* A2005620	TREE, OSTRYA VIRGINIANA (AMERICAN HOPHORNBEAM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	12					12	
* A2007920	TREE, TILIA AMERICANA REDMOND (REDMOND AMERICAN LINDEN), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	9					9	
* B2000566	TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	12					12	
* B2001166	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	11					11	
* B2001666	TREE, CRATAEGUS CRUSGALU INERMIS (THORNLESS COCKSPUR HAWTHORN), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	11					11	
* B2002466	TREE, MAGNOLIA SOULANGIANA (SAUCER MAGNOLIA), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	13					13	
* B2006220	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	9					9	
* X0323444	DECORATIVE STEEL RAILING	FOOT	303		303				

* = SPECIALTY ITEM

PAY ITEM #	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				0004	0011	0021	0031	0042	
X4230710	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH, SPECIAL	SQ YD	357	357					
X4230800	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH, SPECIAL	SQ YD	1,572	1,572					
X5504200	DUCTILE IRON STORM SEWER, 12 INCH	FOOT	84	84					
X6064200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	16,317	16,317					
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1					1	
* X8760055	PEDESTRIAN PUSH-BUTTON POST, TYPE A	EACH	1					1	
XX008003	FORM LINER TEXTURED SURFACE, SPECIAL	SQ FT	982		982				
Z0004518	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 5"	SQ YD	755	755					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	288					288	
* Z0064560	SEGMENTAL BLOCK RETAINING WALL	SQ FT	180					180	
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1,277		1,277				
Z0076600	TRAINEES	HOURL	1,000					1,000	
Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOURL	1,000					1,000	
XX008744	STORM SEWERS, CLASS B, TYPE 2 8"	FOOT	124	124					

PLAN SURVEYED
 PLOTTED
 ALIGNED CHECKED
 NOTE BOOK NO.
 PROFILE NAME

PROFILE SURVEYED
 PLOTTED
 PAVED CHECKED
 NOTE BOOK NO.
 STRUCTURE NOTATION CHRG

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

Hassell Road STP Project
 Summary of Quantities

F.A.U. RTE. 1100	SECTION 11-00087-00-FP	COUNTY Cook	TOTAL SHEETS 164	SHEET NO. 6
CONTRACT NO. 63770				
ILLINOIS FED. AID PROJECT CMM 9603(757)				

SCALE: NTS SHEET NO. 3 OF 4 SHEETS STA. TO STA.

FILE NAME -
 Summary of Quantities.dwg

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -