



- 44000100 PAVEMENT REMOVAL**
 STA. 1008+75 TO 1010+53 - 910.6
 STA. 1011+56 TO 1014+56 - 1584.4
 TOTAL - 2,495.0 SQ YD
- 44000500 COMBINATION CURB AND GUTTER REMOVAL**
 STA. 1009+15.35 TO 1010+55.35, LT - 140.0'
 STA. 1009+25.82 TO 1010+55.35, RT - 129.5'
 STA. 1011+56.72 TO 1014+55.60, LT - 317.3'
 STA. 1011+56.72 TO 1014+55.60, RT - 313.3'
 TOTAL - 900.1'
- 44000600 SIDEWALK REMOVAL**
 STA. 1008+27.64 TO 1010+55.35, RT - 866.3
 STA. 1012+11.59 TO 1014+55.60, LT - 1,254.5
 STA. 1012+11.61 TO 1014+55.60, RT - 1,086.0
 TOTAL - 3206.8 SQ FT
- 55100500 STORM SEWER REMOVAL - 12"**
 STA. 1008+84.67 TO 1008+81.18 - 10.0'
 STA. 1009+02.38 TO 1009+05.76 - 21.0'
 STA. 1008+95.89 TO 1009+05.76 - 19.0'
 TOTAL - 50.0'
- 60500060 REMOVING INLETS**
 1009+02.38, 18.3 LT
 1008+95.89, 21.1 RT
 TOTAL - 2 EACH
- 60500040 REMOVING MANHOLES**
 1008+84.67, 17.5 LT
 1009+05.76, 3.2 RT
 TOTAL - 2 EACH

END IMPROVEMENT
 STATION 1014+56

LEGEND

/// /// ///	TEMPORARY CONSTRUCTION EASEMENT	[R]	STRUCTURE TO BE REMOVED	[Hatched]	SIDEWALK REMOVAL
---	EXISTING R.O.W.	[REC]	STRUCTURE TO BE RECONSTRUCTED	[Hatched]	CONCRETE REMOVAL
- - - -	PROPOSED R.O.W.	[X]	PAVEMENT REMOVAL	[Hatched]	BITUMINOUS REMOVAL
- xxx - xxx -	STORM SEWER REMOVAL	[Shaded]	DRIVEWAY PAVEMENT REMOVAL	[Dashed]	BARRIER CURB REMOVAL
[A]	STRUCTURE TO BE ADJUSTED	[Wavy]	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	[Hatched]	BUILDING TO BE REMOVED (BY OTHERS)

NOTE:
 SEE SHEET EX-1 FOR REMOVAL NOTES.

FILE NAME =	USER NAME = dssdd	DESIGNED - JWM	REVISED -
et:\pwork\pwork\dot\dssdd\0317613\0264750-sht-rem065.dgn		DRAWN - JPF	REVISED -
	PLOT SCALE = 40.0000' / in.	CHECKED - RCH	REVISED -
	PLOT DATE = Mon Dec 17 13:37:04 2012	DATE - \$SUBDATE\$	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**EXISTING REMOVAL PLAN
 JEFFERSON STREET**

SCALE: SHEET NO. 18 OF 18 SHEETS STA. 1008+75 TO STA. 1014+56

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	41R	WINNEBAGO	327	65
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT			CONTRACT NO. 64750	