



LEGEND		NOTES:	
	EXISTING ROADWAY LIGHTPOLE AND LUMINAIRE TO BE REMOVED, SALVAGE		PROPOSED UTILITY POLE (BY OTHERS)
	PROPOSED DECORATIVE LIGHT POLE AND LUMINAIRE ALUMINUM, 40 FT. M.H., PULSE START METAL HALIDE, HORIZONTAL MOUNT 400 WATT (SEE NOTE 13 ON SHEET 487)		PROPOSED LIGHTING CONTROLLER, 100 AMP, 480V
	PROPOSED UNDERPASS LUMINAIRE, METAL HALIDE, VERTICAL MOUNT, 100 WATT		HH = PROP. HANDHOLE PER LATEST DOT STD 8400
	PROPOSED CONDUIT ATTACHED TO STRUCTURE, SIZE AND CONDUCTORS AS INDICATED		PROPOSED UNIT DUCT, 600V, 2-1/C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1/4" DIA. POLYETHYLENE
	PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA. ROADWAY LIGHTING CASING		FD = PROPOSED UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA. WITH PULL STRING AND TRACER CABLE
	PROPOSED JUNCTION BOX		G = PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, SIZE AND CONDUCTORS AS INDICATED

NOTES:
1. REFER TO ROADWAY LIGHTING NOTES ON SHEET 487.

CMT CRAWFORD, MURPHY & TILLY, INC. CONSULTING ENGINEERS License No. 184-026513	MODEL NAME + Oct18	DESIGNED - JWD	REVISED -	2/22/2013
	FILE NAME + D084821-400g1109.dgn	DRAWN - JWD	REVISED -	
	PLOT SCALE + 40.0000 / 1 in.	CHECKED - AB	REVISED -	
	PLOT DATE + 2/22/2013 - 3:45:07 PM	DATE - 11/02/2012	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROADWAY LIGHTING PLAN
IL RTE 2 (SOUTH MAIN STREET)
 SCALE: 1" = 20' | SHEET 9 OF 32 SHEETS | STA. 386+00 TO STA. 392+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	(32, 33) R-1	WINNEBAGO	705	495
				CONTRACT NO. 64821
ILLINOIS FED. AID PROJECT				

DIRECTORY: L:\PROJECTS\1102\1102\1102.dwg User: jason_dave
 USER NAME: Jason Dave