GENERAL NOTES

The final top 6 inches of soil in any right-of-way area disturbed by the Contractor must be capable of supporting vegelation. The soil must be from the A horizon (zero to 2' deep) of soil profiles of local soils.

All Borrow/Waste/Use sites must be approved by the Department prior to removing any material from the project or initiating any earthmoving activities, including temporary stockpiling outside the limits of construction.

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then use Seeding, Class 1. Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches.

Fertilizer Nutrients shall be applied at the rate specified in Sections 250 and 252 of the Standard Specifications. This shall be included in the cost of the SEEDING or SODDING.

A Nationwide 404 Permit has been issued for this project and the conditions of that permit must be adhered to.

This structure will retain the same number 037-2008.

Culvert & bridge flows must be maintained throughout the project. Normal flow shall be allowed to pass at the rate it enters the jobsite. High flows shall be allowed to pass without causing damage to upstream properties.

Where field tile is encountered, storm sewer or pipe drain will be used in accordance with Section 611. The minimum size for replacement will be 6" for Pipe Drains and 8" for Storm Sewer, but the size must be at least 2" larger than the adjoining tile. A Field Tile Junction Vault will be constructed at the right of way to connect the tile and storm sewer. See the Summary of Quantities for the estimated quantities.

Work on this project will be in progress at the same time as work on Contract #64H81, bridge painting over the Mississippi River (ESN 081-0011). Work on these projects shall be scheduled to keep interference between all the projects to a minimum. The contractors shall inform each other of progress of the projects and give fair warning to the other contractors when a problem might be encountered.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

Geneseo Telephone Co. (309/944-8025) MidAmerican Energy/Gas (309/793-3707)

MidAmerican Energy/Elec. (309/793-3833) Windstream (630/925-4751)

IDOT is not a member of JULIE. If you are near any overhead lighting, intersection lighting or traffic signals, contact the IDOT Traffic Office at 815/284-5469 at least 48 hours prior to work.

The applicable portions of Article 105.07 of the Standard Specification shall apply except for the following: The Contractor shall be responsible to locate the vertical depths of the underground utilities which may may interfere with construction operations. This work will not be measured or paid for separately, but shall be considered as included in the unit bid price for the item of construction involved.

Per SB 699 (90 day utility relocation law), once right-of-way is clear to award the project, a notice will be sent to the utility companies instructing them to have their facilities relocated within 90 days. Estimated date relocation complete = Award Date + 100 days

CADD data will be available to Contractors and Consultants working on this project. This information will be provided upon request as MicroStation CADD files and Geopak coordinate geometry files ONLY. If data is required in other formats it will be your responsibility to make these conversions. If any discrepancy or inconsistency arises between the electronic data and the information on the hard copy, the information on the hard copy should be used. Contact the District's Project Engineer to request these files.

All Channel Excavation / Excavated material shall be removed from the project to a site approved by the Department.

The Contractor will be prohibited from washing the extra concrete from the concrete trucks on site.

Clearing and Grubbing required by the contractor for construction access, haut roads, staging areas, and work identified in the plans to complete the specified work will be included in the cost of TREE REMOVAL.

Only those trees called out in the plans for removal will be measured for payment. All trees removed by the contractor for his/her construction access, haul roads, and staging areas will not be measured separately for payment but shall be included in the contract unit cost for INSERTION CULVERT LINER (SPECIAL).

Tree planting layout shall be performed by the District Landscape Architect. Mulch shall be placed 4" thick and to the diameter around the tree as shown on District Standard 92.1. The mulch shall be hardwood wood chips placed on weed barrier fabric. This work shall be included in the cost of the tree.

Erosion Control Blanket shall be applied over all Seeding Class 2A areas. Turf Reinforcement Mat and Seeding Class 4 shall be applied adjacent to the stream banks and in all areas designated for clearing and grubbing behind the concrete headwall.

It shall be the responsibility of the contractor to control the ground water and divert the stream flow during construction in order to keep the construction area free of water. The method of controlling the water shall be subject to approval of the Engineer and the cost shall be included in the contract unit price for INSERTION CULVERT LINER (SPECIAL).

WILLS BURKE KELSEY ASSOCIATES LTD WBK 116 West Main Street, Suite 2 St. Charles, Blooks 69174

REVISED -USER NAME = nporris DRAWN - NOP REVISED . PLOT SCALE : 1:29 CHECKED - RPD REVISED PLOT DATE = 11/38/2012 REVISED

DEPARTMENT OF TRANSPORTATION

SCALE:

COUNTY TOTAL SHEE SHEETS NO. HENRY 27 3 SECTION **GENERAL NOTES** 74/28Q (37-2-1)M CONTRACT NO.64GBO SHEET NO. 1 OF 1 SHEETS STA. TO STA.

STATE OF ILLINOIS