



NOTES:

CULVERT CLEANING

1. CLEANING OF SILT AND DEBRIS FROM EACH 168" CMP PIPE SHALL BE INCLUDED IN THE COST OF DRAINAGE STRUCTURES TO BE CLEANED.

ACCESS

1. SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE TO BE LOCATED AT THE ACCESS POINT DETERMINED BY THE CONTRACTOR AND APPROVED BY THE ENGINEER.
2. ACCESS LOCATION TO THE NORTH AND SOUTH END OF THE CULVERTS TO BE DETERMINED BY THE CONTRACTOR AND APPROVED BY THE ENGINEER.
3. ALL AREAS DISTURBED DUE TO ACCESS SHALL BE RESTORED TO MATCH THE EXISTING CONDITIONS.

CONCRETE WASHOUT

1. THE CONTRACTOR WILL BE PROHIBITED FROM WASHING THE EXTRA CONCRETE FROM THE CONCRETE TRUCKS ON SITE

INSERTION CULVERT LINER (SPECIAL)

1. THE FOLLOWING ITEMS SHALL BE INCLUDED IN THE COST OF THE INSERTION CULVERT LINER (SPECIAL): RAILING SYSTEM, GROUT, BULKHEADS, LINER, AND THE HAUL ROAD.

STAGING AREAS

1. LOCATION AND SIZE OF STAGING AREAS ARE TO BE DETERMINED BY THE CONTRACTOR AND APPROVED BY THE ENGINEER.
2. HAUL ROAD AND STAGING AREAS SHALL BE RESTORED TO MATCH THE EXISTING CONTOURS.

FILE NAME = \\NA\Projects\2010\100120 PTB 157\25\cadd\Civil\Dgn\WD 8\Shr\10264680-act-plan.dgn

WILLS BURKE KELSEY ASSOCIATES LTD.
 116 West Main Street, Suite 201
 St. Charles, Illinois 60174

USER NAME = nparris	DESIGNED -	REVISED -
PLOT SCALE = 1:100	DRAWN - NDP	REVISED -
PLOT DATE = 1/29/2013	CHECKED - RPD	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

GENERAL PLAN

SCALE: 1"=50' SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE. 74/280	SECTION (37-2-1M)	COUNTY HENRY	TOTAL SHEETS 27	SHEET NO. 5
CONTRACT NO. 64680				
ILLINOIS FED. AID PROJECT				