

SCHEDULE OF QUANTITIES

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
	US 20
612.5	Sta 873 + 39 - 879 + 50 Stage I RT
<u>350.0</u>	Sta 874 + 74 - 878 + 13 Stage I LT
962.5	TOTAL

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
	US 20
<u>425.0</u>	Sta 874 + 33 - 878 + 52 Stage II
425.0	TOTAL

70600250 IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION
	US 20
1.0	Sta 874 + 66 Stage I RT
<u>1.0</u>	Sta 878 + 23 Stage I RT
2.0	TOTAL

70600280 IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3

EACH	LOCATION
	US 20
1.0	Sta 873 + 30 Stage I RT
<u>1.0</u>	Sta 879 + 64 Stage I RT
2.0	TOTAL

70600350 IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION
	US 20
1.0	Sta 874 + 20 Stage II
<u>1.0</u>	Sta 878 + 66 Stage II
2.0	TOTAL

78001110 PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION
	US 20
<u>1250.0</u>	Sta 869 + 75 - 882 + 25 White Shoulder LT
<u>1250.0</u>	Sta 869 + 75 - 882 + 25 White Shoulder RT
<u>1250.0</u>	Sta 869 + 75 - 882 + 25 Yellow Centerline EastBound Solid
<u>315.0</u>	Sta 869 + 75 - 882 + 25 Yellow Centerline WestBound Skip
4065.0	SUB-TOTAL X TWO APPLICATIONS
8130.0	TOTAL

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION
	US 20
<u>16.0</u>	Sta 869 + 75 - 882 + 25 80 o.c. Two-way Amber
16.0	TOTAL

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
	US 20
173.6	Sta 869 + 60 - 874 + 86 Stage I - White Shoulder RT
160.4	Sta 878 + 04 - 882 + 90 Stage I - White Shoulder RT
36.6	Sta 869 + 60 - 874 + 02 Stages I & II - Yellow Centerline Dash
32.7	Sta 878 + 95 - 882 + 90 Stages I & II - Yellow Centerline Dash
145.9	Sta 872 + 95 - 874 + 42 Stages I & II - Yellow Centerline Solid
130.4	Sta 878 + 40 - 879 + 61 Stages I & II - Yellow Centerline Solid
<u>371.6</u>	Sta 870 + 95 - 882 + 11 Stage II - White Shoulder LT
1051.2	TOTAL

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION
	US 20
<u>16.0</u>	Sta 869 + 75 - 882 + 25
16.0	TOTAL

X4400110 TEMPORARY PAVEMENT REMOVAL

SQ YD	LOCATION
	US 20
<u>889.0</u>	Sta 872 + 00 - 880 + 79 RT
889.0	TOTAL

Z0054500 ROCK FILL

TON	LOCATION
	US 20
<u>81.0</u>	Sta 876 + 47 (Depth = 6")
81.0	TOTAL

Z0062456 TEMPORARY PAVEMENT

SQ YD	LOCATION
	US 20
<u>889.0</u>	Sta 872 + 00 - 880 + 79 RT
889.0	TOTAL

Z0073002 TEMPORARY SOIL RETENTION SYSTEM

SQ FT	LOCATION
	US 20
114.0	Sta 876 + 03 - 876 + 93 Stage I
<u>114.0</u>	Sta 876 + 03 - 876 + 93 Stage II
228.0	TOTAL

FILE NAME *	USER NAME * hardnetbr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US 20 / IL 84 SCHEDULE OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pridot\hardnetbr\027791910	08711-sht-schedule.dgn	DRAWN -	REVISED -		301	29T-2	JO DAVIESS	52	13			
	PLOT SCALE * 00.0000' / 1"	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 64H17
	PLOT DATE * Mon Dec 18 14:06:32 2012	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							

Rev. 2-20-13