

# SUMMARY OF QUANTITIES

80% FEDERAL  
20% STATE  
0040

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	2,000
* 20200200	ROCK EXCAVATION	CU YD	379
20400800	FURNISHED EXCAVATION	CU YD	1,895
21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SQ YD	1,112
* 25000210	SEEDING, CLASS 2A	ACRE	2.25
*** 25000750	MOWING	ACRE	2.25
* 25100125	MULCH, METHOD 3	ACRE	2.25
25100630	EROSION CONTROL BLANKET	SQ YD	115
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	892
28000305	TEMPORARY DITCH CHECKS	FOOT	100
28000400	PERIMETER EROSION BARRIER	FOOT	1,250
28000500	INLET AND PIPE PROTECTION	EACH	1
28100107	STONE RIPRAP, CLASS A4	SQ YD	132
28200200	FILTER FABRIC	SQ YD	132
30300118	AGGREGATE SUBGRADE IMPROVEMENT 18"	SQ YD	1,268
35101400	AGGREGATE BASE COURSE, TYPE B	TON	261
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	184
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	512
40600990	TEMPORARY RAMP	SQ YD	512
40603310	HOT- MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	370
40603340	HOT- MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	307
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,053
44201359	CLASS C PATCHES, TYPES IV, 10 INCH	SQ YD	250

\* SPECIALTY ITME  
\*\*\* NON- PARTICIPATING 100% STATE

FILE NAME *	USER NAME * hardnetbr	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>US 20 /IL 84 SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\hardnetbr\02779190	00711-eh-500.dgn	DRAWN -	REVISED -		301	291-2	JO DAVIESS	52	5			
PLOT SCALE * 80.8888' / in.		CHECKED -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.			CONTRACT NO. 64H17				
PLOT DATE * Mon Dec 10 14:05:53 2012		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							