

SCHEDULE OF QUANTITIES

30300118 AGGREGATE SUBGRADE IMPROVEMENT 18"

SQ YD	LOCATION
	US 20
1165.0	Sta 872+23 - 882+11 LT SHOULDERS
103.0	Sta 876+03 - 876+93 RT SHOULDERS
1268.0	TOTAL

35101400 AGGREGATE BASE COURSE TYPE B

TON	LOCATION
	US 20
131.0	Sta 876+71 RT Field Entrance
130.0	Sta 880+25 RT Temporary Field Entrance
261.0	TOTAL

40600635 LEVELING BINDER (MACHINE METHOD) N70

TON	LOCATION
	US 20
184.0	Sta 870+30 - 881+70
184.0	TOTAL

40600982 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

SQ YD	LOCATION
	US 20
297.8	Sta 869+75 - 870+50
214.2	Sta 881+50 - 882+25
512.0	TOTAL

40600990 TEMPORARY RAMPS

SQ YD	LOCATION
	US 20
297.8	Sta 869+75 - 870+50
214.2	Sta 881+50 - 882+25
512.0	TOTAL

40603310 HOT-MIX ASPHALT SURFACE COURSE MIX "C" N50

TON	LOCATION
	US 20
179.0	Sta 869+75 - 882+25 RT SHOULDER
191.0	Sta 869+75 - 882+25 LT SHOULDER
370.0	TOTAL

40603340 HOT-MIX ASPHALT SURFACE COURSE MIX "D" N70

TON	LOCATION
	US 20
307.0	Sta 869+75 - 882+25 ROADWAY
307.0	TOTAL

44004250 PAVED SHOULDER REMOVAL

SQ YD	LOCATION
	US 20
1053.0	Sta 872+23 - 882+11 LT SHOULDER
1053.0	TOTAL

44201359 CLASS C PATCHES TYPE IV, 10 INCH

SQ YD	LOCATION
	US 20
250.0	Sta 876+03 - 876+93
250.0	TOTAL

48203019 HOT-MIX ASPHALT SHOULDERS, 5 1/2"

SQ YD	LOCATION
	US 20
1100.0	Sta 872+23 - 882+11 MATCH EXISTING LT
97.0	Sta 876+03 - 876+93 MATCH EXISTING RT
1197.0	TOTAL

50100300 REMOVAL OF EXISTING STRUCTURES NO. 1

EACH	LOCATION
	US 20
1.0	Sta 876+47
1.0	TOTAL

51500100 NAME PLATES

EACH	LOCATION
	US 20
1.0	Sta 876+47
1.0	TOTAL

54011005 PRECAST CONCRETE BOX CULVERTS 10' X 5'

FOOT	LOCATION
	US 20
114.0	Sta 876+47
114.0	TOTAL

5421D015 PIPE CULVERTS CLASS D TYPE 1 1/2" (TEMPORARY)

FOOT	LOCATION
	US 20
67.0	Sta 879+91 - 880+58 38.9' RT
67.0	TOTAL

54215408 CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 8"

EACH	LOCATION
	US 20
1.0	As Needed & Directed by the Resident Engineer
1.0	TOTAL

60100060 CONCRETE HEADWALLS FOR PIPE DRAINS

EACH	LOCATION
	US 20
2.0	Sta 876+03 RT & LT
2.0	TOTAL

FILE NAME : c:\pwork\psidot\hardnetbr\08277919\080711-ehtr-schedule.dgn	USER NAME : hardnetbr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US 20 / IL 84 SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -		301	29T-2	JO DAVIESS	52	11				
		CHECKED -	REVISED -		CONTRACT NO. 64H17								
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								
PLOT SCALE : 00.0000 / in.				SCALE:				SHEET OF SHEETS		STA. TO STA.			
PLOT DATE : Mon Dec 10 14:06:31 2012													