

SUMMARY OF QUANTITIES

GENERAL NOTES

Paycode	Description	Units	0014 State Funds
42001300	PROTECTIVE COAT	SQ YD	34.4
50102400	CONCRETE REMOVAL	CU YD	8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	8
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,100
50800515	BAR SPLICERS	EACH	16
52000110	PREFORMED JOINT STRIP SEAL	FOOT	164
60900240	TYPE C INLET BOX, STANDARD 609006	EACH	2
60900315	TYPE D INLET BOX, STANDARD 609006	EACH	4
67100100	MOBILIZATION	L SUM	1
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	500
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	7,505
70400100	TEMPORARY CONCRETE BARRIER	FOOT	887
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	887
* 78007130	PERMANENT PAVEMENT MARKING - LINE 6"	FOOT	3,786
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,893
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	67.5
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	38.5
70600150	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2

All Borrow/Waste/Use sites must be approved by the Department prior to removing any material from the project or initiating any earthmoving activities, including temporary stockpiling outside the limits of construction.

Temporary Impact Attenuators will be measured as each for each attenuator supplied on the job as specified in the plans, and shall include the cost of renting/owning the attenuator for the time required on the job plus hauling to and from the project site, as well as one placement and removal from the roadway. This shall be paid for at the contract unit price per Each for IMPACT ATTENUATORS, TEMPORARY of the type specified.

Relocate Temporary Impact Attenuators will be paid for as Each and will be paid for each time the attenuator is required by staging to be picked up and moved to a different location on the project, whether it is to another location on the roadway or to a storage/staging location for the project. This shall be paid for at the contract unit price per Each for IMPACT ATTENUATORS, RELOCATE of the type specified.

This work shall be done in accordance with Section 704 of the Standard Specifications. Temporary Concrete Barrier will be measured in feet along the centerline of the barrier and shall include the cost of renting/owning the barrier for the time required on the job plus hauling to and from the project site, as well as one placement and removal from the roadway in accordance with Section 704 of the Standard Specification. This shall be paid for at the contract unit price per Foot for TEMPORARY CONCRETE BARRIER.

Relocate Temporary Concrete Barrier will be paid for in Feet along the centerline of the barrier, and will be paid for each time the barrier is required by staging to be picked up and moved to a different location on the project, whether it is to another location on the roadway or to a storage/staging location for the project. This shall be paid for at the contract unit price per Foot for RELOCATE TEMPORARY CONCRETE BARRIER.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123.

*Specialty Items

22

USER NAME: barlow	DESIGNED: -	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	Summary of Quantities	PLAN SHEET NO.	SECTION	COUNTY	TOTAL SHEET	
PLOT SCALE: 1/4"=1'-0"	DRAWN: -	REVISED: -			1-59	D2 Deck Repair 2013-3	OGLE	18	2
PLOT DATE: Mon Dec 03 07:58:36 2012	CHECKED: -	REVISED: -			CONTRACT NO. 64H95				
	DATE: -	REVISED: -			ILLINOIS				