

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				STATE FUNDS 100% STATE STRUCTURE 0014 RURAL
50606701	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1	L SUM	1	1
50606701	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1	L SUM	1	1
67100100	MOBILIZATION	L SUM	1	1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	1	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	845	845
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	845	845
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1200	1200
78300100	PAVEMENT MARKING REMOVAL	SQ FT	600	600
X5067501	BRIDGE CLEANING AND PAINTING WARRANTY NUMBER 1	L SUM	1	1
X5067502	BRIDGE CLEANING AND PAINTING WARRANTY NUMBER 2	L SUM	1	1
Z0007101	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1
Z0007102	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2	L SUM	1	1
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1	1

* SPECIALITY ITEM

FILE NAME :	USER NAME :	DESIGNED :	REVISED :	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\woodshankr\1148314761\066C56-sht-details.dgn	woodshankr	DRAWN - RW	REVISED -			180	(06-3.78-1)PM	BUREAU	10	3
MODELNAME	PLOT SCALE :	CHECKED :	REVISED :			SCALE:		SHEET 1 OF 1 SHEETS		CONTRACT NO. 66C56
	PLOT DATE :	DATE :	REVISED :			TO STA.		ILLINOIS FED. AID PROJECT		

Rev.