

80% FED.  
20% ST.

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				0004	0005	0011	0011
				ROADWAY		LITTLE SISTER CREEK BRIDGE	BIG SISTER CREEK BRIDGE
				BUILD-UP NONE	OVERLAY NONE	S.N. 029-0073	S.N. 029-0074
40600982	HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	160		160		
40600990	TEMPORARY RAMP	SQ YD	1,120	1,120			
40603000	HOT-MIX ASPHALT BINDER COURSE, IL 12.5, N50	TON	954	954			
40603310	HOT MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	386	386			
40603535	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	620	293	327		
40701861	HOT MIX ASPHALT PAVEMENT (FULL DEPTH), 9"	SQ YD	3,719	3,719			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	48	48			
44000100	PAVEMENT REMOVAL	SQ YD	3,614	3,614			
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	3,952	41	3911		
44004250	PAVED SHOULDER REMOVAL	SQ YD	202	202			
44213200	SAW CUTS	FOOT	775	220	555		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4,146	120	4026		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	911	911			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	88	67	21		

FILE NAME \*  
#FILES



USER NAME * #USER#	DESIGNED - JL / RY	REVISED -
DRAWN - JL / RY	CHECKED - JES	REVISED -
DATE - 12-17-2012		

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
US RTE 24 OVER BIG SISTER CREEK & LITTLE SISTER CREEK

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(137BR, BR-1) BR	FULTON	118	8
ILLINOIS FED. AID PROJECT			CONTRACT NO. 68699	

SCALE: SHEET NO. 3 OF 9 SHEETS STA. TO STA.