

# SUMMARY OF QUANTITIES

| CODE NO  | ITEM   | UNIT  | TOTAL   | CONSTRUCTION CODE |                        |                        |
|----------|--|-------|---------|-------------------|------------------------|------------------------|
|          |  |       |         | ROADWAY           | BRIDGE                 | BRIDGE                 |
|          |  |       |         | 0004<br>URBAN     | 0014<br>S. N. 072-0119 | 0014<br>S. N. 072-0120 |
| 50300255 | CONCRETE SUPERSTRUCTURE  | CU YD | 1295.5  |                   | 649.5                  | 646.0                  |
| 50300260 | BRIDGE DECK GROOVING   | SQ YD | 3479    |                   | 1757                   | 1722                   |
| 50300300 | PROTECTIVE COAT  | SQ YD | 4248    |                   | 2148                   | 2100                   |
| 50400805 | FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN. | FOOT  | 893.5   |                   | 478                    | 415.5                  |
| 50500405 | FURNISHING AND ERECTING STRUCTURAL STEEL                             | POUND | 6980    |                   | 3490                   | 3490                   |
| 50500505 | STUD SHEAR CONNECTORS  | EACH  | 7728    |                   | 3864                   | 3864                   |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED                                     | POUND | 249,370 |                   | 148,550                | 145820                 |
| 50800515 | BAR SPLICERS   | EACH  | 206     |                   | 102                    | 104                    |
| 50800530 | MECHANICAL SPLICERS  | EACH  | 96      |                   | 48                     | 48                     |
| 51500100 | NAME PLATES  | EACH  | 2       |                   | 1                      | 1                      |
| 52000110 | PREFORMED JOINT STRIP SEAL   | FOOT  | 214     |                   | 106.5                  | 107.5                  |
| 52100010 | ELASTOMERIC BEARING ASSEMBLY, TYPE I                                 | EACH  | 32      |                   | 16                     | 16                     |
| 52100530 | ANCHOR BOLTS, 1 1/4"   | EACH  | 64      |                   | 32                     | 32                     |
| 60900240 | TYPE C INLET BOX, STANDARD 609006                                    | EACH  | 4       | 4                 |                        |                        |

• SPECIALTY ITEM

LAST CALLED \* 4/25/2012 \* 10:00 AM \*  
 PLOT SCALE \* 40,000 \* 1/4" \*  
 PLOT DATE \* 12/14/2012 \* 3:48:44 PM \*

USER NAME \* kashbr  
 PLOT SCALE \* 40,000 \* 1/4"  
 PLOT DATE \* 12/14/2012 \* 3:48:44 PM

|            |           |
|------------|-----------|
| DESIGNED - | REVISED - |
| DRAWN -    | REVISED - |
| CHECKED -  | REVISED - |
| DATE -     | REVISED - |

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

## SUMMARY OF QUANTITIES

SCALE: 1" = 20' SHEET NO. 2 OF 6 SHEETS STA. TO STA.

|                              |               |        |                           |           |
|------------------------------|---------------|--------|---------------------------|-----------|
| F.A.I. RTE.                  | SECTION       | COUNTY | TOTAL SHEETS              | SHEET NO. |
| 474                          | (72-3HB-1), 1 | PEORIA | 89                        | 4         |
| MAXWELL RD, CONN. OVER I-474 |               |        | CONTRACT NO. 68883        |           |
| FED. ROAD DIST. NO.          |               |        | ILLINOIS FED. AID PROJECT |           |