

**INDEX OF SHEETS**

- 1. COVER SHEET
- 2-3. GENERAL NOTES/COMMITMENTS
- 4-7. SUMMARY OF QUANTITIES
- 8. TYPICAL SECTION
- 9-11. SCHEDULE OF QUANTITIES
- 12. LINE DIAGRAM
- 13. BENCHMARKS & RECOVERY TIES
- 14-15. EXISTING/REMOVAL PLAN VIEW
- 16-17. PROPOSED PLAN LAYOUT
- 18-19. EROSION CONTROL PLAN VIEW
- 20-24. DISTRICT STANDARDS
- 25-33. CROSS SECTIONS

**Status of Utilities**

Illinois American Water

Route	Offset	Location	Type of Utility	Type of Conflict	Disposition
IL 116	32' RT	255+00 to 275+00	12" Watermain	New ditch line	Relocate

**UTILITIES - LOCATIONS /INFORMATION ON PLANS**

The locations of existing water mains, gas mains, sewers, electric power lines, telephone lines and other utilities as shown on the plans are based on careful field investigation and the best information available, but they are not guaranteed. Unless elevations are shown — all utility locations shown on the cross sections are based on the approximate depth supplied by the utility company. It shall be the Contractor's responsibility to ascertain their exact location from the utility companies and by field inspection.

**PROPERTY OWNER ACCESS REQUIREMENTS**

Access must be maintained to all existing properties during construction per Article 107.09 unless arrangements are made in writing by the Contractor with the property owners with a copy to the Engineer for short-term closures.

**PLAN ELEVATIONS - U. S. G. S. MEAN SEA LEVEL DATUM**

- 1. All elevations shown on the plans are established from U. S. G. S. mean sea level datum.

**ENVIRONMENTAL REVIEWS**

Prior to the use of any proposed borrow areas, use areas (temporary access roads, detours, run-arounds, etc.) and/or waste areas, the Contractor shall file the required environmental resource request surveys according to Section 107.22 of the Standard Specifications. These surveys are required in order for the Department to conduct cultural and biological resource surveys for the proposed site.

Prior to any waste materials being removed from the construction site the required environmental resource surveys will need to be obtained and filed by the Contractor. Excess waste products removed from the construction site shall be disposed of as required in Section 202.03 of the Standard Specifications.

Any protruding metal bars shall be removed prior to the disposal of broken concrete at approved disposal sites.

The required environmental resource documentation shall include the following:

- \* BDE Form 2289 (Environmental Survey Request)
- \* A location map showing the size limits and location of the use area
- \* Signed property owner agreement form-D4 PI0100
- \* Color photographs depicting the use area
- \* Borrow Area Entry Agreement form-D4 PI0101

Please note that a minimum of two weeks shall be allowed for the District to obtain the required environmental clearances.

**PAVEMENT STATIONING NUMBERS & PLACEMENT**

The Contractor shall provide labor and materials required to imprint pavement station numbers in the finished surface of the pavement and/or overlay. The numbers shall be approximately 3/4 inch (20mm) wide, 5 inches (125 mm ) high and 5/8 inch (15 mm ) deep.

The pavement station numbers shall be installed as specified herein:

Interval - 200 feet (English stationing) or 100 meters (metric stationing)

Bottom of Numbers - 6 inches (150 mm ) from the inside edge of the pavement marking

Location:

- \* 2,3, & 5 Lane Pavements - right edge of pavement in direction of increasing stations
- \* Multi-Lane Divided Roadways - outside edge of pavement in both directions
- \* Ramps - along baseline edge of pavement

Position - stations shall be placed so they can be read from the adjacent shoulder

Format - English (Metric) pavement stations shall use this format "XXX (XX+X00)" where X represents the pavement station

This work will not be paid for separately, but will be considered included in the cost of the associated pavement and/or overlay pay items.

FILE NAME * D468A71-ehtrplan.dgn	USER NAME * adustinja	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES/COMMITMENTS</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE * 200.0000 ' / in.	CHECKED -	REVISED -						669	(IR)W-1	PEORIA	33	2
PLOT DATE * 1/4/2012	DATE -	REVISED -	SCALE:		SHEET	OF	SHEETS	STA.	TO STA.	<b>CONTRACT NO. 68A71</b>			
ILLINOIS FED. AID PROJECT													