

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONST. CODE
				PEORIA COUNTY 90% FED. 10% STATE 0004 URBAN
40603080	HOT - MIX ASPHALT BINDER COURSE, IL - 19.0, N50.	TON	1493	1493
40603560	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "E", N50	TON	351	351
44004250	PAVED SHOULDER REMOVAL	SO YD	904	904
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	904	904
48203039	HOT - MIX ASPHALT SHOULDERS, 10 1/2"	SO YD	904	904
50105220	PIPE CULVERT REMOVAL	FOOT	38	38
50800105	REINFORCEMENT BARS	POUND	65	65
54213663	PRECAST REINF. CONC. FLARED END SECTIONS 18"	EACH	1	1
54213669	PRECAST REINF. CONC. FLARED END SECTIONS 24"	EACH	1	1
54215550	METAL END SECTIONS 15"	EACH	2	2
54248510	CONCRETE COLLAR	CU YD	1.1	1.1
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	12	12
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIV. ROUND-SIZE 24"	FOOT	12	12
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	34	34

HMA 2740

FILE NAME \*  
D:\68A71\shs-plan.dgn

USER NAME \* keithbr  
PLOT SCALE \* 100.0000' / in.  
PLOT DATE \* 12/12/2012

DESIGNED -  
DRAWN -  
CHECKED -  
DATE -

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	41RW-1	PEORIA	33	5
			CONTRACT NO. 68A71	
ILLINOIS FED. AID PROJECT				