

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				STP FUNDING 80% FEDERAL 20% STATE ROADWAY 0004	STP FUNDING 80% FEDERAL 20% STATE BRIDGE 0011 S. N. 034-2527
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	148	148	
40600990	TEMPORARY RAMP	SO YD	28	28	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	156	156	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	366	366	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	5	5	
44000100	PAVEMENT REMOVAL	SO YD	1644	1644	
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SO YD	99	99	
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SO YD	80	80	
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SO YD	40	40	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	85	85	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50104400	CONCRETE HEADWALL REMOVAL	EACH	3	3	
50105220	PIPE CULVERT REMOVAL	FOOT	21	21	

• SEE SPECIAL PROVISIONS

FILE NAME * c:\pwork\pwork\pwork\spark\spk\032908\032908\067282.dgn
PLOT DRIVER * PLOTDRVR



USER NAME * sparksgw
FILE NAME * 067282.dgn
PLOT SCALE * 1/8" = 1'-0"
PLOT DATE * 06-18-2012 10:16:54AM

DESIGNED - MCV
DRAWN - CMM
CHECKED - MTM
DATE - 12/12

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 3 OF 7 SHEETS STA. TO STA.

F.A.P. R.I.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685	113B-4	HANCOCK	57	5
CONTRACT NO. 72B62			ILLINOIS FED. AID PROJECT	