

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
				ROADWAY 0004	ROADWAY 0005	SAFETY 0021
				RURAL	RURAL	RURAL
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1			1
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	1		1
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1		1	
54248510	CONCRETE COLLAR	CU YD	0.6	0.3		0.3
54261324	CONCRETE END SECTION, STANDARD 524001, 24", 1:3	EACH	1		1	
54261415	CONCRETE END SECTION, STANDARD 524001, 15", 1:4	EACH	1			1
54261424	CONCRETE END SECTION, STANDARD 524001, 24", 1:4	EACH	1	1		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	344	338		6
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	401	236		165
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	37	23		14
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	13	6		7
60219570	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 3V FRAME AND GRATE	EACH	7	6		1
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2	1		1
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1			1

FILE NAME :	USER NAME : oobrerars	DESIGNED - JWC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pvidot\cebrerars\0259630\02	2E31-shr-soq.dgn	DRAWN - JWC	REVISED -		SCALE:	SHEET 4 OF 11 SHEETS	STA.	TO STA.	(1)N,TS-2RS-5&(7)RS-3	ADAMS	194	6	
Default	PLOT SCALE * 392,7000 */ dm	CHECKED - RSC	REVISED -						CONTRACT NO. 72E31				
	PLOT DATE * Jan-28-2013 01:31:41PM	DATE -	REVISED -						ILLINOIS FED. AID PROJECT				