

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
				ROADWAY 0004 RURAL	ROADWAY 0005 RURAL	SAFETY 0021 RURAL
60500060	REMOVING INLETS	EACH	11	4	1	6
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	46			46
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	254			254
60608582	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	316.5			316.5
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	371.5			371.5
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	107			107
60610900	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 (VARIABLE WIDTH GUTTER FLAG)	FOOT	28.5			28.5
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	3,132			3,132
60622320	CONCRETE MEDIAN, TYPE SM-4.24	SO FT	8,588	7,240		1,348
60622400	CONCRETE MEDIAN, TYPE SM-6.06	SO FT	691			691
60625900	P. C. C. RAMPED MEDIAN TERMINAL	EACH	14	8		6
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	4	4	4
67100100	MOBILIZATION	L SUM	1	0.33	0.33	0.34
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	0.33	0.33	0.34

FILE NAME : c:\pwork\pvidot\cabrera\08254630\72E31-shr-eoq.dgn	USER NAME : cabrera	DESIGNED - JWC	REVISIONS - REVISIONS - REVISIONS - REVISIONS -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION (UN)TS-2RS-5&(7)RS-3	COUNTY ADAMS	TOTAL SHEETS 194	SHEET NO. 7	
PLOT SCALE : 393.7000 / dm	CHECKED - RSC	DATE -	REVISIONS - REVISIONS - REVISIONS - REVISIONS -		SCALE:	SHEET 5 OF 11 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT				
Default	PLOT DATE : Jan-28-2013 8:12:53PM	DATE -	REVISIONS - REVISIONS - REVISIONS - REVISIONS -		CONTRACT NO. 72E31							
* FAP 63 (US 24); FAP 63 (US 24/IL 96); FAP 506 (IL 96)												