

PAVEMENT REMOVAL

44000100

| STATION TO STATION | SIDE | SO YD |
|--------------------|------|-------|
| FAP 502 (IL 57)    |      |       |
| 92+78.7 93+19.5    | RT   | 7.5   |
| LOCK & DAM ROAD    |      |       |
| 9+58.7 9+74.0      | RT   | 2.8   |
| TOTAL              |      | 10.3  |
| USE                |      | 11    |

FURNISHING AND ERECTING RIGHT OF WAY MARKERS

66600105

| STATION         | SIDE | OFFSET | EACH |
|-----------------|------|--------|------|
| FAP 502 (IL 57) |      |        |      |
| 94+09.53        | RT   | 100.00 | 1    |
| 94+50.00        | RT   | 60.00  | 1    |
| TOTAL           |      |        | 2    |

ESTIMATED STRIPING QUANTITIES

| PAY ITEM NUMBER | PAY ITEM                             | UNIT   | QUANTITY | LOCATION/REASON                      |
|-----------------|--------------------------------------|--------|----------|--------------------------------------|
| 70103815        | TRAFFIC CONTROL SURVEILLANCE         | CAL DA | 10       | AS REQUIRED FOR DROP-OFFS            |
| 70300100        | SHORT-TERM PAVEMENT MARKING          | FOOT   | 72       | TEMPORARY STRIPING ON BINDER/SURFACE |
| 70300230        | TEMPORAY PAVEMENT MARKING - LINE 5"  | FOOT   | 1174     | TEMPORARY STRIPING ON BINDER/SURFACE |
| 70300250        | TEMPORAY PAVEMENT MARKING - LINE 8"  | FOOT   | 105      | TEMPORARY STRIPING ON BINDER/SURFACE |
| 70300260        | TEMPORAY PAVEMENT MARKING - LINE 12" | FOOT   | 51       | TEMPORARY STRIPING ON BINDER/SURFACE |
| 70300280        | TEMPORAY PAVEMENT MARKING - LINE 24" | FOOT   | 30       | TEMPORARY STRIPING ON BINDER/SURFACE |
| 70301000        | WORK ZONE PAVEMENT MARKING REMOVAL   | SO FT  | 695      | REMOVE TEMPORARY STRIPING            |

DRIVEWAY PAVEMENT REMOVAL

44000200

| STATION         | SIDE | SO YD |
|-----------------|------|-------|
| FAP 502 (IL 57) |      |       |
| 92+78.0         | RT   | 134.4 |
| TOTAL           |      | 134.4 |
| USE             |      | 135   |

PRISMATIC CURB REFLECTOR

78200300

| STATION TO STATION | SIDE    | MAXIMUM SPACING | EACH |
|--------------------|---------|-----------------|------|
| FAP 502 (IL 57)    |         |                 |      |
| 93+18.5 93+18.5    | LT & RT | N/A             | 3    |
| LOCK & DAM ROAD    |         |                 |      |
| 9+58.7 9+74.0      | RT      | 10              | 9    |
| TOTAL              |         |                 | 12   |

PREFORMED PLASTIC PAVEMENT MARKING  
TYPE B - INLAID - LINE 24"

78004280

| STATION TO STATION | SIDE | DESCRIPTION | WHITE FOOT |
|--------------------|------|-------------|------------|
| LOCK & DAM ROAD    |      |             |            |
| 9+50.4 9+64.2      | RT   | STOP BAR    | 18.0       |
| 9+64.4 9+64.4      | RT   | STOP BAR    | 12.0       |
| TOTAL              |      |             | 30.0       |
| USE                |      |             | 30         |

CURB REMOVAL

44000300

| STATION TO STATION | SIDE | FOOT |
|--------------------|------|------|
| FAP 502 (IL 57)    |      |      |
| 92+41.4 92+57.4    | RT   | 19.0 |
| 93+03.0 93+27.1    | RT   | 26.0 |
| TOTAL              |      | 45.0 |
| USE                |      | 45   |

MODIFIED URETHANE PAVEMENT MARKING - LINE 5"

78009005

| STATION TO STATION | SIDE    | DESCRIPTION | WHITE FOOT | YELLOW FOOT |
|--------------------|---------|-------------|------------|-------------|
| FAP 502 (IL 57)    |         |             |            |             |
| 92+32.7 92+67.2    | RT OS   | EDGE LINE   | 64.5       |             |
| 93+12.0 93+18.5    | LT IS   | EDGE LINE   |            | 8.5         |
| 93+12.0 93+18.5    | RT IS   | EDGE LINE   |            | 8.5         |
| 95+50.0 95+75.0    | LT IS   | EDGE LINE   |            | 50.0        |
| 95+50.0 95+75.0    | RT IS   | EDGE LINE   |            | 50.0        |
| LOCK & DAM ROAD    |         |             |            |             |
| 7+50.0 9+74.0      | LT      | EDGE LINE   | 252.0      |             |
| 7+50.0 9+64.4      | LT & RT | NO-PASSING  |            | 428.8       |
| 7+50.0 9+74.0      | RT      | EDGE LINE   | 311.0      |             |
| TOTALS             |         |             | 627.5      | 545.8       |
| USE                |         |             |            | 1174        |

CURB AND GUTTER REMOVAL

44000500

| STATION TO STATION | SIDE | FOOT  |
|--------------------|------|-------|
| FAP 502 (IL 57)    |      |       |
| 92+32.7 93+13.0    | RT   | 80.4  |
| 94+72.6 95+13.7    | RT   | 41.0  |
| LOCK & DAM ROAD    |      |       |
| 8+43.1 9+67.6      | LT   | 150.5 |
| 8+65.8 9+73.8      | RT   | 153.8 |
| 9+60.7 9+74.0      | RT   | 39.3  |
| TOTAL              |      | 465.0 |
| USE                |      | 465   |

MODIFIED URETHANE PAVEMENT MARKING - LINE 8"

78009008

| STATION TO STATION | SIDE | DESCRIPTION | WHITE FOOT |
|--------------------|------|-------------|------------|
| LOCK & DAM ROAD    |      |             |            |
| 9+44.8 9+74.0      | RT   | ISLAND      | 104.4      |
| TOTAL              |      |             | 104.4      |
| USE                |      |             | 105        |

MEDIAN REMOVAL

44003100

| STATION TO STATION | SIDE    | SO FT |
|--------------------|---------|-------|
| FAP 502 (IL 57)    |         |       |
| 93+12.0 93+37.7    | LT & RT | 102.6 |
| 95+50.0 95+75.0    | LT & RT | 100.0 |
| TOTAL              |         | 202.6 |
| USE                |         | 203   |

MODIFIED URETHANE PAVEMENT MARKING - LINE 12"

78009012

| STATION TO STATION | SIDE | DESCRIPTION | WHITE FOOT |
|--------------------|------|-------------|------------|
| LOCK & DAM ROAD    |      |             |            |
| 9+44.8 9+74.0      | RT   | ISLAND      | 50.1       |
| TOTAL              |      |             | 50.1       |
| USE                |      |             | 51         |

MEDIAN SURFACE REMOVAL

X4403800

| STATION TO STATION | SIDE | SO FT |
|--------------------|------|-------|
| LOCK & DAM ROAD    |      |       |
| 9+58.7 9+74.0      | RT   | 71.6  |
| TOTAL              |      | 71.6  |
| USE                |      | 72    |