

INDEX OF SHEETS

1. COVER
2. INDEX OF SHEETS, GENERAL NOTES, AND HIGHWAY STANDARDS
3. SUMMARY OF QUANTITIES
4. TYPICAL SECTIONS
5. SCHEDULES
6. PLAN

HIGHWAY STANDARDS

- 701001-02
- 701006-04
- 701201-04
- 701301-04
- 701306-03
- 701311-03
- 701501-06
- 701901-02
- 780001-03

GENERAL NOTES

1. THE CONTRACTOR SHALL GIVE IDOT OPERATIONS TWO WEEKS NOTICE PRIOR TO STARTING WORK IN ORDER FOR IDOT TO COMPLETE PATCHING.
2. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
3. NO EXCAVATION IS ANTICIPATED ON THIS PROJECT. SHOULD ANY EXCAVATION BE REQUIRED, J.U.L.I.E. SHALL BE NOTIFIED A MINIMUM OF 48 HOURS IN ADVANCE (800) 892-0123.
4. ALL CONFLICTING EXISTING STRIPING SHALL BE REMOVED.
5. ALL PAVEMENT MARKINGS, AND NO PASSING ZONES SHALL BE FIELD VERIFIED BY DISTRICT 6 OPERATIONS (785-5312) 14 DAYS PRIOR TO FINAL PAVEMENT MARKINGS.
6. PAVEMENT MARKINGS SHALL NOT BE APPLIED UNTIL AGGREGATE IS PROPERLY SEATED.
7. ADDITIONAL BROOMING (UP TO 3 TIMES) SHALL BE REQUIRED AT THE DISCRETION OF THE ENGINEER, INCLUDING THE DAY OF PERMANENT PAVEMENT MARKING.
8. LOOSE ROCK/GRAVEL AND SUGGESTED 45 mph SIGNS SHALL BE ERECTED AND MAINTAINED UNTIL THE PERMANENT PAVEMENT MARKINGS HAVE BEEN COMPLETED.
9. TEMPORARY PAVEMENT MARKING - LINE 5' SHALL BE PAINT, MARKING TAPE WILL NOT BE ALLOWED.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6	
EXAMINED <u>12/18</u>	20 <u>12</u>
<i>William Boyd</i> ENGINEER OF OPERATIONS	
EXAMINED <u>12/13</u>	20 <u>12</u>
<i>Jimmy J. [Signature]</i> ENGINEER OF PROJECT IMPLEMENTATION	
EXAMINED <u>Dec 14</u>	20 <u>12</u>
<i>2RMIJ</i> ENGINEER OF PROGRAM DEVELOPMENT	

FILE NAME *	USER NAME * Sherptd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, HIGHWAY STANDARDS AND GENERAL NOTES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pw_work\pwidot\sherptd\0317779\06722	79-shr*gennote.dgn	DRAWN -	REVISED -			566	(23,24)-1	LOGAN	6	2	
Default	PLOT SCALE * 2.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 72F79					
	PLOT DATE * Dec-18-2012 06:39:57AM	DATE -	REVISED -			SCALE:	SHEET 1 OF 1 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	