SUMMARY OF QUANTITIES				CONSTR. CODE URBAN 100% STATE
				ROADWAY 0005
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	13	13
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1
40600300	AGGREGATE (PRIME COAT)	TON	3	3
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	22	22
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	1730	1730
40600990	TEMPORARY RAMP	SQ YD	282	282
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	117	117
44004250	PAVED SHOULDER REMOVAL	SQ YD	32	32
48203100	HOT-MIX ASPHALT SHOULDERS	TON	94	94
60260100	INLETS TO BE ADJUSTED	EACH	8	8
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	90	90
63300575	REMOVE AND REERECT RAIL ELEMENT OF EXISTING GUARDRAIL	FOOT	436	436
67100100	MOBILIZATION	L SUM	1	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1

SUMMARY OF QUANTITIES				CONSTR. CODE URBAN 100% STATE
				ROADWAY 0005
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	3	3
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4
70300100	SHORT TERM PAVEMENT MARKING	FOOT	177	177
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	22	22
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	130	130
* 78009005	MODIFIED URETHANE PAVEMENT MARKING - LINE 5"	FOOT	998	998
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	18	18
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	18	18
Z0012500	CONCRETE CURB REPAIR	FOOT	5	5
Z0021916	SILICONE JOINT SEALER, 3"	FOOT	41	41
Z0041895	POLYMER CONCRETE	CU FT	3	3

* SPECIALTY ITEM