

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE
				0004 URBAN	0011 S.N. 048-6063
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	113	113	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	109	109	
20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25	
20200100	EARTH EXCAVATION	CU YD	545	545	
20400800	FURNISHED EXCAVATION	CU YD	5495	5495	
20800150	TRENCH BACKFILL	CU YD	15	15	
Δ 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4738	4738	
Δ 25000100	SEEDING, CLASS 1	ACRE	1	1	
Δ 25000300	SEEDING, CLASS 3	ACRE	0.25	0.25	
Δ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	104	104	
Δ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	104	104	
Δ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	104	104	
Δ 25100630	EROSION CONTROL BLANKET	SQ YD	4583	4583	
Δ 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	1391	1391	
Δ 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	18	18	
28000305	TEMPORARY DITCH CHECKS	FOOT	133	133	
28000400	PERIMETER EROSION BARRIER	FOOT	1003	1003	
28000500	INLET AND PIPE PROTECTION	EACH	3	3	
28100105	STONE RIPRAP, CLASS A3	SQ YD	19	19	
28200200	FILTER FABRIC	SQ YD	19	19	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1250	1250	
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	37	37	
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	48	48	
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1	
40600300	AGGREGATE (PRIME COAT)	TON	2	2	
40603230	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	424	424	
40603510	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	201	201	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	35	35	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	112	112	
44000100	PAVEMENT REMOVAL	SQ YD	1404	1404	

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE
				0004 URBAN	0011 S.N. 048-6063
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	219	219	
50157300	PROTECTIVE SHIELD	SQ YD	98		98
50200100	STRUCTURE EXCAVATION	CU YD	116		116
50300225	CONCRETE STRUCTURES	CU YD	168.2		168.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	390.6		390.6
50300260	BRIDGE DECK GROOVING	SQ YD	689		689
50300300	PROTECTIVE COAT	SQ YD	1085		1085
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	3960		3960
50800105	REINFORCEMENT BARS	POUND	10560		10560
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	115,470		115,470
50800515	BAR SPLICERS	EACH	114		114
50800530	MECHANICAL SPLICERS	EACH	224		224
51201400	FURNISHING STEEL PILES HP10X42	FOOT	642		642
51202305	DRIVING PILES	FOOT	642		642
51204650	PILE SHOES	EACH	12		12
51500100	NAME PLATES	EACH	1		1
51603000	DRILLED SHAFT IN SOIL	CU YD	52.3		52.3
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12		12
52100520	ANCHOR BOLTS, 1"	EACH	24		24
52100530	ANCHOR BOLTS, 1 1/4"	EACH	24		24
542A2749	PIPE CULVERTS, CLASS A, TYPE 4 24"	FOOT	130	130	
542C0217	PIPE CULVERTS, CLASS C, TYPE 1 12"	FOOT	43	43	
54213447	END SECTIONS 12"	EACH	2	2	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	198	198	
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	14	14	