

54213447 END SECTIONS 12"	
LOCATION	EACH
STA. 61+89.59, 53.3' LT	1
STA. 62+49.49, 43.6' LT	1
<b>TOTAL</b>	<b>2</b>

54213657 PRECAST REINFORCED FLARED END SECTIONS 12"	
LOCATION	EACH
STA. 63+64.94, 37.4' RT	1
<b>TOTAL</b>	<b>1</b>

54213663 PRECAST REINFORCED FLARED END SECTIONS 18"	
LOCATION	EACH
STA. 58+00.00, 67.4' RT	1
<b>TOTAL</b>	<b>1</b>

54213669 PRECAST REINFORCED FLARED END SECTIONS 24"	
LOCATION	EACH
STA. 59+07.51, 62.7' LT	1
STA. 59+01.90, 75.4' RT	1
<b>TOTAL</b>	<b>2</b>

550A0050 STORM SEWERS, CLASS A, TYPE 1 12"	
LOCATION	FOOT
STA. 56+73.01, 15.0' LT TO STA. 56+73.01, 15.0' RT	30.0
STA. 56+74.51, 16.0' RT TO STA. 58+01.53, 52.6' RT	132.2
STA. 62+82.90, 15.1' LT TO STA. 62+83.53, 14.7' RT	29.8
STA. 63+64.59, 31.3' RT TO STA. 63+64.94, 37.4' RT	6.1
<b>TOTAL</b>	<b>198</b>

550A0120 STORM SEWERS, CLASS A, TYPE 1 24"	
LOCATION	FOOT
STA. 58+02.66, 54.5' RT TO STA. 58+00.00, 67.4' RT	13.2
<b>TOTAL</b>	<b>14</b>

550A0640 STORM SEWERS, CLASS A, TYPE 3 12"	
LOCATION	FOOT
STA. 63+84.90, 16.7' RT TO STA. 63+62.75, 29.9' RT	70.2
<b>TOTAL</b>	<b>71</b>

60218400 MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	
LOCATION	EACH
STA. 58+02.97, 53.0' RT	1
STA. 63+64.51, 29.8' RT	1
<b>TOTAL</b>	<b>2</b>

60236200 INLETS, TYPE A, TYPE 8 GRATE	
LOCATION	EACH
STA. 58+24.60, 75.1' LT	1
<b>TOTAL</b>	<b>1</b>

60600095 CLASS SI CONCRETE (OUTLET)	
LOCATION	CU YD
STA 55+50.00, RT	0.6
<b>TOTAL</b>	<b>0.6</b>

60603800 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	
LOCATION	FOOT
STA. 55+64.00 TO STA. 58+88.12, RT	317.5
STA. 55+50.00 TO STA. 58+91.19, LT	350.5
STA. 61+10.25 TO STA. 62+89.73, RT	185.5
STA. 61+10.25 TO STA. 62+89.73, LT	173.5
<b>TOTAL</b>	<b>1027</b>

X6330725 STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	
LOCATION	FOOT
STA. 61+19.69, 30.1' RT TO STA. 61+26.69, 53.8' RT	25
<b>TOTAL</b>	<b>25</b>

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6	
LOCATION	EACH
STA. 58+73.57 TO STA. 59+19.75, RT	1
STA. 58+79.17 TO STA. 59+19.75, LT	1
STA. 60+80.25 TO STA. 61+24.00, LT	1
<b>TOTAL</b>	<b>3</b>

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	
LOCATION	EACH
STA. 58+32.79 TO STA. 58+79.17, LT	1
STA. 61+24.00 TO STA. 61+74.28, LT	1
STA. 58+20.68 TO STA. 58+73.57, RT	1
<b>TOTAL</b>	<b>3</b>

63200310 GUARDRAIL REMOVAL *	
LOCATION	FOOT
STA. 8+95.88, 17.3' RT TO STA. 9+26.66 12.1' RT	31.2
STA. 8+95.52, 19.0' LT TO STA. 9+26.69, 14.3' LT	31.2
STA. 10+74.21, 14.1' RT TO STA. 11+14.48, 25.8' RT	44.6
STA. 11+39.29, 25.3' RT TO STA. 13+00.95, 15.3' RT	168.7
STA. 10+72.02, 11.1' LT TO STA. 13+03.95, 16.6' LT	227.5
<b>TOTAL</b>	<b>504</b>

67000500 ENGINEERS FIELD OFFICE, TYPE B	
LOCATION	CAL MO
ENTIRE PROJECT	9
<b>TOTAL</b>	<b>9</b>

67100100 MOBILIZATION	
LOCATION	L SUM
ENTIRE PROJECT	1
<b>TOTAL</b>	<b>1</b>

X7016500 TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)	
LOCATION	EACH
STA. 54+27.55, 14.5' RT	---
STA. 54+49.48, 15.5' LT	---
STA. 56+38.74, 21.0' RT	---
STA. 56+45.37, 20.4' RT	---
STA. 63+85.63, 18.0' RT	---
STA. 63+81.65, 24.9' LT	---
STA. 64+21.82, 24.4' RT	---
<b>TOTAL</b>	<b>1</b>

70400100 TEMPORARY CONCRETE BARRIER	
LOCATION	FOOT
STA. 55+50.00 TO STA. 62+99.04	750
<b>TOTAL</b>	<b>750</b>

78009004 MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	
LOCATION	FOOT
STA. 55+50.00 TO STA. 58+89.74	1479.5
(DUAL YELLOW)	1480
<b>TOTAL</b>	<b>1480</b>

X6060097 CLASS SI CONCRETE (OUTLET), SPECIAL	
LOCATION	CU YD
STA 55+39.50, LT	0.64
STA 55+39.50, LT	0.23
<b>TOTAL</b>	<b>0.9</b>

78100100 RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	EACH
STA. 55+50.00	1
STA. 56+30.00	1
STA. 57+10.00	1
STA. 57+90.00	1
STA. 58+70.00	1
STA. 61+90.00	1
STA. 062+70.00	1
<b>TOTAL</b>	<b>7</b>

78100105 RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	
LOCATION	EACH
STA. 59+50.00	1
STA. 60+30.00	1
STA. 61+10.00	1
<b>TOTAL</b>	<b>3</b>

X7240300 *	
LOCATION	EACH
STA. 5+49.17, 19.7' RT	1
STA. 6+60.71, 20.0' RT	1
STA. 13+27.27, 14.6' LT	1
STA. 14+00.00, 34.0' LT	1
<b>TOTAL</b>	<b>4</b>

X7240500 *	
LOCATION	EACH
STA. 5+51.80, 17.2' LT	1
STA. 12+08.84, 22.2' RT	1
<b>TOTAL</b>	<b>2</b>

Z0028462 GEOTEXTILE RETAINING WALL	
LOCATION	SQ FT
STA. 56+00.00 TO STA. 57+25.00, LT	189
<b>TOTAL</b>	<b>189</b>

X7010216 TRAFFIC CONTROL AND PROTECTION (SPECIAL)	
LOCATION	L SUM
ENTIRE PROJECT	1
<b>TOTAL</b>	<b>1</b>

70600240 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	
LOCATION	EACH
STA. 55+50.00, 1.0' LT	1
STA. 62+98.00, 3.2' RT	1
<b>TOTAL</b>	<b>2</b>

Z0048665 RAILROAD PROTECTIVE LIABILITY INSURANCE	
LOCATION	L SUM
ENTIRE PROJECT	1
<b>TOTAL</b>	<b>1</b>

Z0043750 PRECAST MODULAR BLOCK WALL	
LOCATION	SQ FT
STA. 61+69.71 TO STA. 62+22.62, LT	120
<b>TOTAL</b>	<b>120</b>

Z0013798 CONSTRUCTION LAYOUT	
LOCATION	L SUM
ENTIRE PROJECT	1
<b>TOTAL</b>	<b>1</b>

60626500 TRANSITIONAL COMBINATION CONCRETE CURB AND GUTTER	
LOCATION	FOOT
STA. 55+49.85, LT	10
STA. 55+84.00, RT	10
<b>TOTAL</b>	<b>20</b>

\* UTILIZES EXISTING ROADWAY STATIONING

FILE NAME : S:\237\2012\23712001.00 (Soangetaha Road)	USER NAME : jdspliller	DESIGNED : BT	REVISED :
DRAWN : BT/WLL	CHECKED : RJA	DATE :	REVISED :
PLOT SCALE : 40.0000 / 1 in.			
PLOT DATE : 1/7/2013			



CITY OF GALESBURG

SOANGETAHA ROAD  
SCHEDULES

SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.	M.S.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
							651	07-00651-03-BR	KNOX	67	7
										CONTRACT NO. 89625	
										ILLINOIS	