

**CLASS SI CONCRETE (OUTLET) SCHEDULE**

STATION	CLASS SI CONCRETE (OUTLET) (CU YD)
HERITAGE BIKEWAY	
STA. 114+06.23 - 15.41' RT TO STA. 114+17.48 - 16.07' LT	1.66
STA. 114+32.02 - 15.92' RT TO STA. 114+40.66 - 15.76' LT	1.63
STA. 114+13.29 - 48.39' RT TO STA. 114+29.39 - 21.39' RT	1.54
STA. 163+79.99 - 7.14' RT TO STA. 163+80.14 - 13.42' RT	0.5
<b>TOTAL</b>	<b>5</b>

**BOLLARD ASSEMBLY SCHEDULE**

STATION	BOLLARDS (EACH)	FOLD DOWN BOLLARDS (EACH)
HERITAGE BIKEWAY		
STA. 103+54.81 - 34.00' LT	2	1
STA. 113+81.52 - 0.24' LT	2	1
STA. 114+68.79 - 1.35' LT	2	1
STA. 128+70.62 - 0.81' LT	2	1
STA. 129+50.82 - 0.04' RT	2	1
STA. 163+42.36 - 0.14' LT	2	1
STA. 164+42.85 - 0.70' LT	2	1
STA. 191+68.57 - 1.81' RT	2	1
STA. 198+09.10 - 0.77' LT	2	1
STA. 217+55.84 - 8.93' RT	1	
STA. 217+73.93 - 8.56' RT	1	
STA. 282+06.81 - 165.59' RT	2	1
STA. 284+78.37 - 144.50' RT	2	1
STA. 290+00.33 - 35.80' LT	2	1
STA. 354+14.47 - 0.06' RT	2	1
STA. 355+00.12 - 2.05' RT	2	1
STA. 363+53.76 - 1.57' RT	2	1
STA. 364+57.31 - 0.26' LT	2	1
STA. 369+43.75 - 0.30' LT	2	1
STA. 440+08.69 - 5.20' RT	2	1
STA. 440+97.43 - 6.56' RT	2	1
STA. 461+04.86 - 3.42' RT	2	1
STA. 461+83.42 - 2.97' RT	2	1
STA. 495+24.04 - 2.45' LT	2	1
STA. 495+96.61 - 2.04' LT	2	1
<b>TOTAL</b>	<b>48</b>	<b>23</b>

**REMOVE AND RE-INSTALL PIPE CULVERTS SCHEDULE**

STATION	REMOVE AND RE-INSTALL PIPE CULVERTS (FOOT)
HERITAGE BIKEWAY	
STA. 352+07.38 - 26.42' RT TO STA. 352+10.03 - 18.87' RT	8
STA. 352+23.29 - 18.87' LT TO STA. 352+25.95 - 26.42' LT	8
<b>TOTAL</b>	<b>16</b>

**EROSION CONTROL BLANKET SCHEDULE**

STATION	EROSION CONTROL BLANKET (SQ YD)
HERITAGE BIKEWAY	
STA. 228+32.56 - 10.02' LT TO STA. 229+57.56 - 8.21' LT	29.3
STA. 228+32.56 - 9.99' RT TO STA. 229+57.56 - 5.80' RT	35.1
STA. 233+84.21 - 10.41' RT TO STA. 238+21.96 - 7.98' RT	378.0
STA. 351+16.66 - 6.96' LT TO STA. 353+16.66 - 7.56' LT	202.6
STA. 351+16.66 - 7.04' RT TO STA. 353+16.66 - 6.43' RT	234.3
STA. 423+25.00 - 6.10' LT TO STA. 427+75.00 - 6.57' LT	132.1
STA. 423+25.00 - 7.91' RT TO STA. 427+75.00 - 7.43' RT	244.2
STA. 471+00.00 - 8.82' LT TO STA. 474+75.00 - 5.83' LT	82.3
STA. 470+25.00 - 8.03' RT TO STA. 473+50.00 - 10.62' RT	479.6
STA. 479+75.00 - 8.61' LT TO STA. 483+25.00 - 6.83' LT	324.5
<b>TOTAL</b>	<b>2142</b>

**PIPE CULVERTS TO BE CLEANED 24" SCHEDULE**

STATION	PIPE CULVERT TO BE CLEANED 24" (FOOT)
HERITAGE BIKEWAY	
STA. 220+88.53 - 22.50' LT TO STA. 220+97.74 - 56.93' RT	80
<b>TOTAL</b>	<b>80</b>

**CHAIN LINK FENCE SCHEDULE**

STATION	CHAIN LINK FENCE, 6' (FOOT)
HERITAGE BIKEWAY	
STA. 218+46.60 - 27.17' LT TO STA. 218+47.19 - 27.35' RT	69.4
STA. 220+67.39 - 17.51' RT TO STA. 220+68.63 - 16.98' LT	40.4
STA. 282+67.33 - 13.33' LT TO STA. 282+67.58 - 13.43' RT	32.3
STA. 283+33.65 - 13.00' LT TO STA. 283+33.69 - 14.16' RT	33.9
<b>TOTAL</b>	<b>176</b>

**PROTECTIVE COAT**

STATION	PROTECTIVE COAT (SQ YD)
HERITAGE BIKEWAY	
P.C.C. SIDEWALK 6 INCH	195
P.C.C. DRIVEWAY PAVEMENT	15
CLASS SI CONCRETE (OUTLET)	24
<b>TOTAL</b>	<b>234</b>

**INFORMATION KIOSK SCHEDULE**

STATION	INFORMATION KIOSK COMPLETE (EACH)
HERITAGE BIKEWAY	
STA. 103+70.07 - 55.74' LT	1
STA. 129+59.20 - 19.42' LT	1
STA. 282+36.42 - 117.70' RT	1
STA. 354+00.91 - 17.53' RT	1
STA. 463+20.51 - 38.69' RT	1
<b>TOTAL</b>	<b>5</b>