

STRUCTURE SCHEDULE

ITEMS	UNITS	GRAND TOTAL	STRUCTURE NO. 1	STRUCTURE NO. 2	STRUCTURE NO. 3	STRUCTURE NO. 4	STRUCTURE NO. 5	STRUCTURE NO. 6	STRUCTURE NO. 7	STRUCTURE NO. 8	STRUCTURE NO. 9	STRUCTURE NO. 10	STRUCTURE NO. 11	STRUCTURE NO. 12	STRUCTURE NO. 13	STRUCTURE NO. 14	GOSHEN TRAIL BRIDGE
STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	211							90					121			
FURNISH AND ERECT SIGN PANEL	SQ FT	72							24			24					24
REMOVAL OF EXISTING STRUCTURE, SPECIAL	EACH	9	1	1	1	1	1	1		1	1		1				
PAINT REMOVAL	SQ FT	11000							7820			3180					
* DEBRIS REMOVAL	L SUM	9	1	1	1	1	1	1		1	1		1				
WOOD RAIL	FOOT	744	58	58	82	76	58	58		58	58		58	24	60	96	
TREE REMOVAL, ACRES	ACRES	0.20	0.05		0.02	0.03	0.01	0.06		0.01	0.01		0.01				
CHANNEL EXCAVATION	CU YD	1335	80	160	155	120	175	110		245	100		190				
FURNISHED EXCAVATION	CU YD	300	105	15	75	40				50	15						
AGGREGATE BASE COURSE, TYPE A	CU YD	123												123			
POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	153	17	17	17	17	17	17		17	17		17				
STONE RIPRAP, CLASS A4	SQ YD	1030								350	310		370				
STONE RIPRAP, CLASS A5	SQ YD	1940		395	430	320	490	305									
STONE RIPRAP, CLASS A6	SQ YD	585	585														
FILTER FABRIC	SQ YD	3555	585	395	430	320	490	305		350	310		370				
HOT MIX ASPHALT SURFACE COURSE MIX "C", N50	TONS	30										10		20			
BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	126	14	14	14	14	14	14		14	14		14				
CONCRETE ENCASEMENT	CU YD	18	5.0	10.0	2.0								1.0				
TREATED TIMBER	FBM	85315	12025	11085	9079	7311	8791	7138		10703	8496		10687				
WATERPROOFING MEMBRANE SYSTEM	SQ YD	236												236			
EPOXY CRACK INJECTION	FOOT	13							10			3					
BOX CULVERTS TO BE CLEANED	FOOT	256							200			56					
PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	358															358
RUB RAIL	FOOT	261															261
PAVEMENT REMOVAL (SPECIAL)	SQ YD	180															180
STAINLESS STEEL BANDS	FOOT	154		74				21					59				
TIMBER BEAM REPAIR	L SUM	1	1														
CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1															1
CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1															1
BRIDGE DECK CONCRETE OVERLAY	SQ YD	35															35
COFFERDAM (TYPE 1) (LOCATION-1)	EACH	1	1														

* FOR INFORMATION ONLY, INCLUDED IN EARTH EXCAVATION PAY ITEM.